

# Service Information (PCB Logic)



## PURSUIT

# TABLE OF CONTENTS

Α.	INTRODUCTION/WARRANTY	1
В.	NEW MACHINE SET-UP PROCEDURE	2
С.	SERVICE ACCESS	2
D.	NEW MACHINE CHECKOUT	3
Ε.	PLAY	5
F.	CIRCUITS	9
G.	SET-UP PROCEDURE	21
н	PRODUCTION BOARD TESTS	23
Ι.	MOTOROLA MONITOR	25
J.	Q-530 COIN ACCEPTOR ADJUSTMENT & MAINTENANCE	27
Κ.	GENERAL MACHINE MAINTENANCE	29
L.	TROUBLESHOOTING	30
М.	P.C.B. SHIPPING	33

#### A. INTRODUCTION/WARRANTY

PURSUIT is a video amusement device which simulates flying a fighter plane.

This game has been designed with solid state circuitry to be as maintenance free as possible. However, as with all devices mechanical or electrical, there may be minor problems. If the printed circuit board (PCB) fails within the 90 day\*warranty period, contact the distributor from whom the game was originally purchased for replacement or repair instructions. All such warranty returns must be accompanied by completed warranty return forms. Any PCB repairs attempted by anyone other than authorized Atari Service Center personnel will void the warranty. If the PCB fails after the warranty period has expired, it will be repaired for a nominal parts and labor charge.

Atari, Inc. warrants the T.V. monitor for a period of 30 days commencing the day of shipment from the Atari factory. If the monitor fails within that period, immediately contact the distributor from whom the game was originally purchased for repair or replacement instructions. Any T.V. repairs (other than replacement of fuses or adjustments) attempted during the warranty period by anyone other than authorized Atari Service Center personnel will void the warranty.

If the T.V. monitor fails <u>after</u> the warranty period has expried, it may be returned to the distributor where it will be repaired for a nominal parts and labor charge, or it may be taken to any competent T.V. repair shop

\*(From date of shipment from the factory)

#### B. NEW MACHINE SET-UP PROCEDURE

Before turning this machine on, inspect it carefully for any damage which may have occurred during shipment. Inspect both interior and exterior of the machine for any obvious damage to the cabinet or internal components. Check for cracked or broken cabinet parts, assemblies pulling loose, broken or disconnected wires or foreign objects shorting electrical connections. After the machine has been plugged in and turned on, perform the checkout procedure.

#### C. SERVICE ACCESS

All servicing is performed at the rear of the machine through the rear door which provides access to all components, sub-assemblies, and adjustments with the exception of the coin box. The coin door is located on the front of the machine underneath the control panel. To remove the coins, unlock the metal coin door and open. This exposes the coin box.

To reach the interior of the machine, unlock and remove the rear door. Please note that an interlock switch is provided for this door so that the machine is completely turned off whenever this door is opened. These switches protect the operator from accidental shock and so they must always be kept in perfect working order. If the machine is adjusted or tested with the rear door open, the interlock switch must be placed in the closed (or "on" position) by pulling out the white actuator shafts.

<u>wARNING</u>: The covered black terminal block carries full line voltage <u>whenever</u> the line plug is connected to a power outlet. This cover should be removed only with the line plug disconnected. Do not leave off the cover once it has been removed.

#### D. NEW MACHINE CHECKOUT

As each new machine leaves the factory, every component and subassembly is carefully checked for proper operation. However, since parts may have been damaged or adjustments changed during shipping, the following checkout procedure must be repeated prior to placing the machine on location:

- Inspect both the exterior and interior of the machine for obvious shipping damage such as cracked or broken cabinet parts, subassemblies broken loose, etc.
- 2. Carefully inspect the interior of the machine to see that all solder joints, slip-on connectors and plug-in type connectors are firmly seated. Pay particular attention to the PCB edge connector, the fuses and the connectors to the potentiometers. Also check the connections to the coin switch, the T.V. monitor, the interlock switches and all the other Molex-type connectors.
- 3. Plug the machine in, and pull out the white actuator shafts of the interlock switches if the rear door is open. Inspect the CRT (cathode ray tube) image for a steady and sharp picture which exhibits the proper levels of brightness and contrast.
- 4. Insert several old and new coins into the coin acceptor. No genuine coin should be rejected and each coin insertion should step the coin counter one digit. Depress the coin rejector button to make sure that the linkage is operating smoothly.
- 5. Coin insertion should start the game. (Check for proper game sequence, making sure that all aspects of the game i.e. plane display and control, score count and display, etc. are functioning correctly. If you are not familiar with the game sequence for Pursuit, read the game sequence description.

- 6. The door locks should turn to the "locked" and "unlocked" positions smoothly and the doors should open and close without binding.
- 7. The interlock switches must turn off the entire machine when the rear door is opened. (See the "WARNING" under Section C).

	100-1100	-
E	PI	AY.

Picture:

Joystick moves forward and backward and from side to side.

In the preceding figure, the view is from the cockpit of a Pursuit airplane. The cross hairs are the sights of an airplane-mounted machine gun.

Control is with a joystick. Pushing the joystick forward causes the airplane to dive. Backward, it causes the airplane to climb. Turning right is accomplished by moving the joystick to the right, and turning left is accomplished by moving the joystick to the left. This is exactly how a real World War I Pursuit aircraft was controlled.

Attract Mode: (1) Enemy aircraft (being followed) remains on the screen.

It will normally wander randomly up and down and from side to side.

Occasionally it will stick on edge awaiting random circuit instructions to push it back towards the center of the screen.

- (2) Sound is shut off in attract mode permitting machine gun to be fired continuously. This is evident by a flashing spot of light in the center of the cross hairs.
- (3) If the wandering enemy aircraft moves through the center of the cross hairs, it will be shot down. A shoot down is followed by an explosion sequence. The enemy disappears while the debris of the destroyed aircraft radiates outward from the center. In the latter half of the explosion sequence, a new airplane reappears on the screen. Another plane is chalked up on the scoring strip on the right hand side of the screen.

Play Mode: The enemy aircraft moves randomly as in the attract mode, but now we control our airplane to shoot him down. If the enemy is below us we dive to get him. Pushing the stick forward does this. The horizon is seen to move up while we get nearer to getting the enemy into the gun sights. Conversely, if the enemy is high we climb to get him. The horizon moves down as we get closer. Engine sounds are present in the play mode and they change depending on whether we are climbing or diving.

If the enemy is to the right or left we move the stick sideways to catch him. A motion to the right causes the cross hairs to tilt right simulating the bank of the other airplane. The machine gun is fired by pressing the button on top of the joystick. In addition to flashes of light in the center of the cross hairs, a machine-gun sound comes from the speaker.

A hit results in the explosion of the enemy with the attendant picture of flying debris (see Attract Mode), but we also have the explosion noise. The noise is slightly delayed from the hit. There are 2 series of explosions. The enemy disappears from the screen during the first explosion but he reappears during the second explosion.

Scoring and game time are recorded on the left and right sides of the screen.

Play time shows up as a bar on the left. This is intended to simulate a gas gauge. It starts as a bar that extends to the top. As the game procedes it shortens until at the end of the game it disappears. Extended play results in a gas tank refill occurring at the skill level that has been set into the PCB with coded switches.

Scoring is done with small marker planes on the right side. A hit marks one plane (light) on the upper right. A score of 15 (light) airplanes is possible, then the score restarts at the top with dark markers. 30 is the maximum recorded score. In addition to score marks, the illuminated tags are as follows:

- 4 WASHOUT
- 8 STUDENT PILOT
- 12 EAGLE
- 16 ACE

Switches on the PCB enable setting to any of these levels for Extended Play. For example, if Extended Play is set for EAGLE, then when EAGLE is attained the game time starts over again. This is seen as a refill of gas. At the end of the game sound and control cease.

## F. CIRCUITS

- Coin and game time. Schematic region CC6, DD6, 7.
  - a. Devices Q5  $A8_{11}A8_8A7_4B6_{12}Q6_1A7_2$ ,  $A8_6E6$ , D7,  $A6_3$
  - Game starts when a voltage is applied at terminal 18. This b. is also the terminal to which the coin counter is connected. Current to the coin counter flows through the coin switch. According to cherry switch this current helps keep this switch operational. Diode CR13 holds down voltage spikes. Voltage must be at terminal 18 long enough for C36 to integrate up to Q5 conduction (.7V). Q5 sets Flip Flop  $A8_{11-8}$  when it conducts. A8 is a Hysterisis device to give extra protection against noise or sparks triggering the game ON. C23 also helps prevent this. GT means GAME TIME and is used in the same sense as ATTRACT is used in other games. When GT is TRUE 555 timer (E6) is released to operate (Terminal 4). E6 operates in the A stable mode. 8 cycles of operation comprise a Game. These cycles of operation are counted in 7493-D7. The termination count is when the 4's significant FF comes ON. This goes through B6, A6 and A7 to reset the Game FF  $(A8_{11-8})$ . When power is first applied to the game or an interruption in power occurs, the Q6 circuit assures that game time will be in the OFF state. The rising 5V charging C37 causes Q6 to conduct and reset via A6 and A7.
- 2. Game time display. Schematic region DD6-EE6
  - a. Devices  $C7_{11,8,6}B7_{12,6,4,2}-A7_4$ ,  $C6_4$ ,  $D4_8$ ,  $A7_8$

- b. The game time count is compared to functions V32,64, and 127 in C7. When scan has moved down the screen to the point that comparison is TRUE, this result is latched in C64. The "moving down" vertical signal is ANDed with A functions in D48 to generate the fuel video bar.
- 3. Score, Memory and Display. Schematic region CC5,6 DD5 EE5.
  - a. Devices  $L6_3F7_6$ ,  $L8_8$ ,  $J4_{12}J7$ ,  $J6_{6,11,83}...K6_{6,10,8,4}...K3_1$ ,  $K3_4$ ,  $N4_{13}$ ,  $K4_{11}K4_8$ ,  $L4_3$ ,  $L4_{11}$ ,  $K4_3K3_{13-10}$ ,  $D4_6$ ,  $M4_8$ ,  $A7_1$   $F6_{2-10-4}$ ,  $C6_9$ , Q9, Q10, Q11, Q8, Q12
  - b. Score memory is 5 bit counter L6, J7. At GT score is reset to "zero" via L613 and B66. Score is accumulated by counting explosion pulse arrowing from  $L6_5$ . Score is compared with Functions V16, V32, V64 and V128 in comparison to J6 to generate a pulse when vertical scan moves down to the amount of score count. The occurance of this compare is stored in FF, K3<sub>11</sub>, K34. The correct number of score marks (airplanes) is gated in at  $D4_5$ . Airplane shape is formed at inputs 1,2, and 4 to D4.  $FF-N4_{13}$  and  $K4_{11}$  form the "line" for score wings. The major position of the score body is formed in  $L4_{3-11}$  and  $K4_3$ . Further shaping and vertical segmentation is done by  $K3_{13}$  and  $K3_{10}$ . Exclusive gate M4<sub>8</sub> is used to reverse the polarity of the score signal from white to black for score counts 15 to 30. At count of 15 is by  $J4_{12}$  and the connection to  $L6_4$  causes the least significant bit to be forced to ONE on the next count. This is done for skip count 15-17 as polarity of score changes. Otherwise there would have been no score showing at the 16th

score. Score is decoded at H7 for operating skill lights (H7 is BCD to decimal order). DIP switch P6 selects level at which extended play starts (4 to 8, 12, or 16). When the extended play level is reached FF C6 $_9$  is set lighting EXT PLAY lamp and resetting fuel to full via A7 $_2$ A8 $_6$ . A8 $_6$  is a hysterisis gate and is operated in this circuit as a monostable detecting rising voltage (FF-C6 $_9$  coming ON).

- 4. Sound circuits. Schematic region DD5, EE5-6-7-8/
  - a. Devices QX, N3, Q1, N2, K8, N8, N5, LM380,  $M8_6L8_2$ Q17.
  - Machine gun sound is generated by discharging capacitor C43 through the speaker voice coil. The machine gun pulses operate relay L10 to do this. R118, CR8, CR11 are noise suppression components to limit kickback from speaker inductance due to machine gun operation. C43 recovers its charge between shots through R115. Machine gun sound is enabled only during GT (M81). The fact that audio from LM380 is disabled during machine gun sounds is scarsely discernable, but this causes considerable distortion of explosion sounds. Therefore, explosion disables the machine gun  $(M8_2)$ . The explosion sound is constructed from a noise source (Al and N2) and a solid variable gain amplifier QX and CA3080. Noise is generated by Q1 which is a 2N3643 whose base to emitter junction is forced into an avalance (Zener) mode by applying 15 volts through 680K. In this mode white noise is generated. The noise is amplified by N2 to the extent that some clipping occurs.

Noise is input to CA3080 at Pin 3 after the attenuation of 6.8K/150K. The CA3080 amplifies fully when QX pulls up pin 5. The rate of pull-up is controlled by R13. The rate of decay is controlled by R12. Motor sounds are generated digitally in A stable Multi K8 (LM555) and counter 7493 N9. The basic frequency is generated in K8. This frequency is changed to indicate climbing or diving by a varying D.C. input from the horizon circuit (MS at AA2). The airplane engine sound is constructed from Fundamental and appropriate mixing of harmonics. This mixing is done across R120. The highest frequency comes via R117. The next frequency down is a contribution of differentiated spikes via C35. The lowest frequencies are added via R119 and R118. Explosion is normally simulated by a sharp rise in break up sound with a relative slow fading of this sound. In Pursuit, the rise is also slow. A normal explosion is made up of 2 separate explosions as controlled by explosion counter N7. (BB5).

- 5. Power Supply. Schematic Region CC7-8, DD6-8.
  - a. Devices. (CR6 CR7) for scoring lights CR11 CR12, LM309.
  - b. Five volts is supplied by the TV chassis. The 5 volt wire is larger than the other wires in the cable to minimize voltage drop. For 15 volts the unfiltered voltage appears across C42. The divider R112 and R113 changes the LM309 from a 5 volt regulator to a 15 volt regulator. Actually it is connected as a 10 volt regulator with a +5 volt as ground reference. This was done to increase the accuracy of the +15 volts. A diode (CRX) is connected from +5 volts

to +15 volts to prevent the +15 volts from being much lower than 5 volts at turn on. This situation could cause lock up of the 15 volt supply. Lamp power is supplied unfiltered from CR6 and CR7.

- 6. Timing Circuits. Schematic region 3 and 4 all across schematic.
  - a. Devices  $Al_{all}$ , C1, D1, D2, E3, D3, C3, B3 A3,  $C2_{all}$ ,  $E4_{all}$ ,  $A5_{all}$ ,  $H3_{8-12-10}$ ,  $B2_{all}$ ,  $B1_{all}$ ,  $A2_{all}$ ,  $E2_{10-13}$ ,  $A1_{8}$ .
  - b. A new crystal frequency is used in Pursuit. This frequency was selected because the logic functions that it generated in division divides the screen in a much more symmetrical way. This can be appreciated by operating the explosion circuit and observing the symmetrical function radiants outward from the exact center of the screen.

A ripple counter is used throughout. To avoid problems with ripple propagation, intergate pulses BT and MF are generated near the beginning to supply levels that occur only after all settling has occured. The division to horizontal drive frequency is divided by (256 x 3). There are no counter resets required although the divide by 3 counter D2 accomplishes the divide by 3 from the logical feedback via B23. The vertical fields are interlaced as in TV but with 544 lines per frame instead of 525. Division for vertical and slower functions continues through C3, B3 and A3. Wave form diagrams are supplied for horizontal and vertical functions.

Video Circuit. Schematic region DB and DD4, C4, Q5.
 a.

- b. The video mixing circuit picks up the various picture components and mixing occurs at the junction of these mixing resistors. A.C. coupling to the TV is through C40. Q15 inserts H and V sync signals that are forced negative TRUE. This deletes video during sync resulting in a steady picture. A separate input to the video mixing is provided for convenience when testing.
- 8. Cross hair circuit. Schematic region AA and BB 7,8 and 9.

Devices E8<sub>2</sub>, E8<sub>1</sub>, F7.

b. Counters L2 and K2 and J1 to H1 are compared to vertical and horizontal timing functions to lines for the cross hairs. When there is no tilt, the counters are loaded at Pin 11 of the counters. The counters being set to center number generate only straight lines when compared to timing functions. It and HI being compared to horizontal will generate a vertical line when the count number is center. L2 and K2 set to center and compared to vertical functions generates a horizontal line.

When a tilted line is to be generated the counters are preset to ZERO. (Pin 14). While L2-K2 generate the straight horizontal line, the tilted line is essentially horizontal. N4 generates a narrow window tin the center of the screen in which the tilted line is to be generated. When this window opens the counter starts to count and ti will have counted through to 256 by the time the window closes. If the cross hair tilt is to be to the left, the count pulses are counted UP  $(J2_6)$ . Thus at the top of the picture the comparator writes a spot at the left of the window. On subsequent lines the comparison is farther and farther to the right. The result is a slanted line.

If the tilt is to be to the right,  $J2_8$  is enabled causing count down. While the counter starts at reset (ZERO), the first count down put it at 256, and we write a line slanting to the left. Jl and Jl generate the horizontal slanting line in an analogous manner, except that the window is a V function and the count H functions. Raw cross hair video is solid when there is no slant. There is no way to avoid dotted lines when there is slant. Therefore, to make the cross hairs consistant  $F1_{11}$ ,

F1<sub>8</sub>, K7<sub>10</sub>, E1<sub>6</sub>, E1<sub>12</sub>, F1<sub>6</sub> circuits are used to break up the lines for uniform appearance, and to gate out undesired portions.

- 9. Machine Gun Circuit. Schematic region AA5.
  - a. Devices M7, L7,  $K7_{all}$ , M8, L8<sub>4</sub>, F7<sub>3</sub>.
  - b. Machine gun pulses are developed in counter, M7. V6 is counted (1/60 second). During game time reset is released by trigger. The audio portion of the count is decoded EM and DM at M8 $_6$  (EE8) to operate the speaker. K7 $_{1,13}$  L7 $_1$  decodes a narrow vertical line. L7 $_{18,4,13}$  decodes a narrow horizontal line. The AND of these signals at M8 $_8$  gives Bullet Video. Bullet Video is a spot at the center of the screen. There is also a spot at center-bottom but this is to be ignored.
- 10. Explosion Circuit. Schematic region BB and CC-5 and AA6.
  - a. Devices: N6, M6, M4<sub>3-11</sub>, J4<sub>6</sub>, L4<sub>8</sub>, K4<sub>6</sub>, L8<sub>6</sub>, P1<sub>a11</sub>, N1<sub>a11</sub>, M1<sub>6-12-8</sub>, L1<sub>6,9,11</sub>, F6<sub>8</sub>, F5<sub>8</sub>.
  - b. The explosion is an expanding window in which successively larger blocks blink ON and OFF. The largest WINDOW is WFN3 which is a larger square taken in the center of the display. WFNZ and WFNI are successively smaller. XFNI and 2 are broken block functions. The above functions are multiplied in N6 and M6 to give the expanding explosion function.

- 11. Analog Motion. Schematic region AA and BB1.
  - a. Devices: Q7,  $N5_{10}$ ,  $H8_{1,7}$ ,  $E8_{14,13}$ , Q16, Q14, Q12, Q13 and

Random Target Motion Control: Schematic region AA and BB 1 and 2. Devices  $A8_3$ , B8,  $D8_{a11}$ ,  $N5_{2-4-6-8}$ , Q4, Q3,  $M5_{12-6}$ ,  $N4_4$ ,  $E1_8$ ,  $E2_{1-4}$ .

b. The analog motion circuit outputs at  ${\rm H8}_1$  and  ${\rm H8}_7$ . The output is in the form of a DC voltage representing position on screen. When this voltage is at about 7.5 volts (reference BB2), the target should be at center of the screen. Comparator  ${\rm E8}_{14-13}$  and V-H ramp circuits translate the analog voltage for the digital circuits. The analog voltages are normally always changing. H8 and H8 $_7$  being integrator will continually change in the direction of the input currents.

Input currents are supplied at H8<sub>2</sub> and H8<sub>6</sub> from 3 sources. Source #1 is from the joystick pots and this arrives as the current junction via R50 and R76. Source #2 is random motion. This comes via R68 and R59. Source #3 is via R51 and R77 and this is predominantly bounce components intended to keep the target either on the screen and/or to prevent the integrator from saturating. A saturated integrator would result in a large time delay before the target can be pulled away from the edge of the picture. The bounce circuit is operated by changing or discharging C34 and C33. When the target is moving around in the central area of the picture, the bounce capacitor is charged only through R49 or R75. This is nominally towards ZERO voltage with respect to reference. In other words, towards "no effect". The small effect that these resistors

have is to give motion some inertia to more realistacally simulate real airplane behavior. At 1.2 meg, this effect is very small. However, if it is desired to change game characteristics, this could be changed. When the target moves to the edge logic circuits  ${
m M5}_{12-6}$  and  ${
m E2}_{1-4}$  operate  ${
m N5}_4$  to  ${
m N5}_8$  for charging capacitor or  ${\rm N5}_2$  to  ${\rm N5}_6$  for discharging the capacitor. This action either forcefully bounces the target away from the edge or keeps sufficient charge to the capacitor to prevent integrater saturation. If integrator saturation is prevented, random motion summary current will certainly sooner or later push the target back towards center. This is more important in attract than in game because in game the joystick is used to pull the target to the center. Neutral voltage at the joystick pots during game time should be at the reference level, hence giving no motion bias. At mechanical neutral, the resistance on each side of the arm is unbalanced at 1K and 4K. Balance is recovered with on board pots connected on the low resistance side of each hoystick control. These pots are used for compensating all game time off center bias. At attract time the control pots are disconnected by conduction of Q7. At this time centering of both borizontal and vertical target motion is done with the 250 ohm attract center pot. Random motion is always imparted to the target by current inputs to the summary junction via R65,64,61,63,66 and 62. For each of horizontal and vertical the values are roughly in the ratio of 4-2-1, giving a D/A conversion of the digital inputs from  $\mathrm{D8}_{1}$ . Voltages higher than reference give down or right motion, whereas voltages less than reference give up or left motion. The most significant bit from D8<sub>12</sub> or D8<sub>2</sub> is essentially the direction bit. Random digital input to D8 is

obtained from B8 (74164) which is a serial in parallel out 8 bit shift register. The input to the shift register is oscillator A83. The shift register is advanced about every 2 seconds. The value that happens to be at the input at shift time is the value that is shifted through the shift register. Since advance time is asynchronous with respect to the free running oscillator, the value at this time is random. As the bit shifts its significance charges allowing the total change instructed to also be random.

- 12. Digital Motion Circuit. Schematic region DD and EE1.
  - a. Devices: D5<sub>all</sub>, E5<sub>all</sub>, F5<sub>12-10</sub>, H5, J5, H6, L5<sub>3</sub>.
  - b. Prior to a compare of DC input, H8<sub>1</sub> with a ramp at E8<sub>9</sub> the output at E8<sub>14</sub> is down. This down condition holds D5<sub>13</sub> (latch) up unconditionally. When E8<sub>14</sub> rises upon detecting compare, D5<sub>13</sub> is enabled to come down, but it will not do so until DT comes down. DT is a negative going signal of 25% duty cycle that is exactly out of phase with MF. Since detection of compare can occur only at a synchronous condition with DT an interface is established from the analog signal which can occur at any time to a synchronous system that has forbidden times.

The negative signal is transmitted through  $\mathrm{E5}_8$  to release latch  $\mathrm{D5}_9$  and to  $\mathrm{D5}_1$ . At that time both 1 and 2 of  $\mathrm{E5}$  are up giving a negative output at  $\mathrm{E5}_3$ . This negative condition is quickly terminated when  $\mathrm{D5}_9$  is reset by MF.

The overall result is a very short negative pulse guaranteed to occur at compare. This negative pulse resets HT window counters H5 and H6, which count through once. Count is stopped by a down condition at K5. (The most significant bit of the counter). While counting through the target functions are generated. The generation of the vertical target function is completely analogous.

- 13. Target form circuits. Schematic region DD and EE2.
  - a. Devices: A4<sub>a11</sub>, B4<sub>a11</sub>, F4<sub>1,10,4</sub>, F1<sub>3</sub>, C5<sub>a11</sub>, A4<sub>a11</sub>, A6<sub>8</sub>, K5<sub>8-11</sub>.
  - b. Wings, body and fins are ORed at 4, 3, and 5 of C5 respectively. Gate  $A6_8$  is disabled during explosion  $(A6_{10})$  to cause target to disappear for a moment.
- 14. Horizon. Schematic region AA and BB2.
  - a. Devices: H8<sub>8</sub>, H8<sub>14</sub>.
  - b. The vertical joystick voltage is amplified by  ${\rm H8}_8$  and compared to the vertical ramp with  ${\rm H8}_{14}$ . R73 and R74 give hysterisis to smooth transition when a change of direction occurs. The step function generated at  ${\rm H8}_{14}$  is the horizon voltage. The changing voltage at  ${\rm H8}_8$  is used to change motor sound.

## G. SETUP PROCEDURE

## (1) Instruments Required

- (a) Watch or clock for timing.
- (b) Micronta 22-205A 20,000 ohm/volt meter or equivalent
- (c) Mirror to observe screen while adjustments are made at board.

## (2) Motion Centering Adjustment

- (a) Make sure adjustment tabs on each of the joystick pots are centered and secured. We use RTV to secure these tabs.
- (b) Center the joystick mechanically. This should be the position to which spring loading holds the joystick.
- (c) Adjust H balance on board until there is ZERO volts between reference junction R39-R40 and the H control arm. Use a Micronta meter on .5 volt scale.
- (d) Same as (3) except on V joystick pot.
- (e) While meter is connected between V arm and reference, turn game OFF (interrupt power), and adjust ATTRACT center control for ZERO volts.
- (f) Using clip leads short C27 and C24.
- (g) Adjust V and H ramp to center target. Explosions will occur but position can still be observed in at least half of this sequence.

## (3) Extended Play Adjustment

The extended play switch is located at P6 on the PCB. It is a 4 pole DIP switch. Each of the poles enables extended play at the skill level of:

- 1. Wash Out
- 2. Eagle

Note reversed sequence

- Student Pilot
- 4. Ace

If all switches are OFF no extended play occurs. Only one switch should be ON at a time.

## (4) Game Time Adjustment

Location: About D6 on board.

Orientation: Face is from top of board.

Adjustment: Clockwise increases game time.

Range: 1/2 minute to 3.5 minutes.

## (5) Sound (Volume Control)

Location: About N9

Orientation: Facing is from top of board.

Adjustment: Clockwise to increase volume.

## H. PRODUCTION BOARD TESTS

- (1) Instruments Required:
  - (a) Oscilloscope
  - (b) Test station with display and analog controls.
- (2) Suggest logical sequence of investigation. A given circuit cannot be assured of work until all that is before it has been confirmed to be functional. (Can be changed as experience dictates).
  - (a) Power Supply
  - (b) Timing chain to Pix Sync.
  - (c) Game Time circuits
  - (d) Analog input adjustment
  - (e) Confirm proper analog motion as varying DC at H8 1 and 7.
  - (f) Confirm H and V ramp at E3 9 and 11.
  - (g) Confirm H and V "step" signals at E8 14 and 13.
  - (h) Trigger pulse should exit at  $E_{3}$  & 11. These pulses are very short and at  $E_{11}$  may be difficult to see.
  - (i) Check for H and V window at  ${\rm H6_6}$  and  ${\rm L5_2}$ .
  - (j) Check for structure of target body through to video.
  - (k) Check for porper motion of target in response to control input and random motion input.
  - (1) If no random motion check oscillation  $A8_3$  and shift register B8.
  - (m) If target sticks check H and V bounce circuits.
  - (n) Horizon video.
  - (o) Bullet circuits
  - (p) Explosion couter  $L6_5$  to N7.
  - (q) Explosion video.
  - (r) Explosion sounds. If more check audio.

- (s) Motor sounds. If more check audio.
- (t) Audio output.
- (u) Machine gun sounds.
- (v) Cross hair circuits.

## NOTES

- (a) R110 on PCB provides a video input point so that circuit may be probed in the video display mode. This point is at E10 and is marked "TP".
- (b) Balance control must be adjusted to match the test station analog controls. See setup procedure. This setup procedure must be repeated later with controls used in actual game.

#### MOTOROLA MONITOR

Monitor circuitry includes four stages of video amplification - a two stage audio amplifier, sync and deflection circuits, and a regulated power supply. An additional 5 volt supply is included to power the external logic system. The rear panel controls work as in any normal T.V. - vertical, horizontal, brightness and contrast. The vertical and horizontal controls should be set in the middle of their range. Turn control until picture tears or rolls, turn control back until picture tears or rolls in the opposite direction and reset control in the middle of the stable range. The brightness and contrast should be set at a point where the images on the screen do not smear. Additional controls are mounted on the printed circuit board (PCB) and are accessible from the rear of the chassis. These include vertical size, vertical linear, focus, etc.

- 1. Five Volt Supply: This is located on the power, audio PCB which is on the left side of the monitor in back of the power transformer. There is a 1,000 ohm trim pot to adjust the supply voltage. This measurement should be made on the logic PCB to allow for voltage drop from monitor to PCB.
- 2. Regulator Adjustment: Connect monitor to AC line supply. Adjust horizontal and vertical controls until display is synced. Connect precision voltmeter to any of the 73 volt test points and adjust regulator control R74 on circuit board for an output of 73 volts. CAUTION: Do not run the regulator control through its range or damage to the monitor may result. All that needs to be done is a slight turn to adjust properly. Both the 5 volt and 73 volt adjustments have been made at the factory and under normal

- conditions should not need readjustment.
- 3. The Yoke: The yoke should never need adjustment unless the adjusters have been tempered with or the machine damaged. If yoke adjustment is indicated, adjust both yoke rings <u>simultaneously</u> for optimum centering of the image on the CRT. This adjustment is best handled by a qualified service person.
- 4. A.C. Voltage Switch: Set this switch to the 115V position ("115" visible on the switch) if the machine is connected to a 115V source or to the 230V position ("230" visible on the switch) if the machine is connected to a 230 volt source. The T.V. monitor will not function if this switch is misadjusted. NOTE: If the monitor of a 230 volt machine is set to 115 volts, it will blow the machine line-fuse repeatedly.
- 5. The T.V. Monitor Fuse: One 6/10-amp, 250-volt fast-blo fuse protects the T.V. from electrical overload (for 155V operation, the T.V. fuse must be 1-amp <u>fast-blo</u>.) Replace blown fuses with ONLY those which have the above rating. This fuse is located on the electronics mounting board inside the rear door. The fuse furthest from the door is the T.V. fuse, and the fuse nearest the door is the P.C.B. fuse. The P.C.B. fuse should be replaced ONLY with a one-amp, slo-blo, 250-volt fuse.

#### Monitor P.C.B. Removal:

(a) Power, Audio PCB: Locate board on the left side of the monitor in back of the power transformer. To remove, pull board up. To replace board, locate the slot between pins 3 and 4 and put this on your left side, then simply insert into the connector. (b) Monitor PCB: To remove the monitor PCB take a screwdriver or similar object and slowly pry the PCB up off of the chassis until it clears the pins. Next, unplug the socket from the yoke and slide board out. To replace this board, follow the above steps in reverse order.

The monitor can be removed by way of the rear access door of the cabinet. This door also provides access to the logic PCB, transformer assembly, score light PCB and main harness connectors. CAUTION: Any work performed on monitor chassis should be done only by qualified service personnel who are familiar with

## J. Q-530 COIN ACCEPTOR: OPERATION, ADJUSTMENT & MAINTENANCE

servicing procedures and precautions.

1. Adjustment: All coin acceptors leave the factory adjusted for maximum performance. If, however, more critical adjustments are desired, or if the unit has been completely disassembled for service, the following adjustment procedure is suggested. If the coin acceptor has been removed from the machine, place it in a vertical position on a level surface. If the acceptor is still mounted on the coin door, place the coin door in a vertical position on a level surface.

## Kicker and Separator

- Set the acceptor with the back of the unit facing you in the test position.
- Loosen the screws holding the kicker (1) and the separator (3)
   and move both the kicker (2) and the separator (4) as far to
   the right as they will go. Tighten the screws.

- Insert several test coins (both old and new) and note that some are returned by striking the separator.
- Loosen the separator screw and move the separator a slight amount to the left. Tighten the screw.
- 5. Insert the test coins again and, if some of them are still returned, repeat Step 4 until all the coins are accepted.
- Loosen the kicker screw and move the locker as far to the left as it will go. Tighten the screw.
- 7. Insert the test coins and note that some are returned.
- Loosen the kicker screw and move the kicker a slight amount to the right. Tighten the screw.
- Insert the coins again and, if some are still returned,
   repeat Step 8 until all the coins are accepted.
- 10. Be sure that both screws are tight after the adjustments have been made.

#### The Magnet Gate

- Set the acceptor with the front of the unit facing you in the test position.
- Turn the magnet gate adjusting screw (2) out (counterclockwise)
   until none of the coins will fit through.
- With a coin resting in the acceptor, turn the adjuster in (clockwise) until the coin barely passes through the magnet gate.
- 4. Test this adjustment using several other coins (both old and new) and, if any of them fail to pass the magnet gate, repeat Step 3 until all the coins are accepted.
- Fix the magnet gate in this position with a drop of glue or lok-tite, if necessary.

Acceptor Maintenance: Depending on the environment in which the acceptor is used, periodic preventitive maintenance should be performed. The mainplate (5) may be cleaned with any household cleaner. Thorough rinsing and drying are necessary to remove deposits and/or film. Remove all metal particles from the magnet by guiding the point of a screwdriver or similar tool along the edges of the magnet. You will notice that the particles will cling to the point of the tool. Remove the transfer cradle (9) and the undersize lever (10) and clean the bushings and the pivot pins. A pipe cleaner is an effective cleaning tool. Apply powdered graphite or pencil lead to the pivot pins and bushings and reassemble. Spray the entire unit lightly with WD-40, a silicone lubricant.

## K. GENERAL MACHINE MAINTENANCE

Due to its solid state circuitry, your Pursuit will require very little maintenance other than periodic cleaning, lubrication and T.V. monitor adjustment. The cabinet and plexiglass screen may be cleaned with any non-abrasive household cleaner. The coin acceptor and the rejector linkage should be sprayed lightly once every three months with WD-40 or similar silicone lubricant. The potentiometer shafts must never be lubricated in any way. The T.V. monitor is adjusted only when the CRT picture is distorted, or if the contrast or brightness appear to be out of adjustment.

#### L. TROUBLESHOOTING

The first step in any troubleshooting procedure is to identify the observable characteristics of the malfunction. With these clues in mind, examine the areas of the machine which might cause these symptoms. For example, if there is no power, check the harness - not the PCB. Likewise, if part of the playfield display is missing, check the PCB - not the harress or TV.

Three major areas of the machine can be isolated for troubleshooting purposes: the T.V., the PCB and the harness. The harness includes the fuses, the transformer, the interlock switches, the A.C. line filter, the start and coin switches, the antenna wire, the potentiometers, all plug-in type connectors, the PCB edge connector and all the interconnecting wires.

- Substitution: Substitution of parts is a legitimate and easy way
  to troubleshoot the machine. For instance, if you suspect PCB
  malfunction try substituting another and known-to-be-good PCB.
  To check the T.V. monitor by substitution, connect the malfunctioning game to a known-to-be-good monitor. Harnesses are checked
  by elimination. Substitute a good T.V. and PCB and if the
  malfunction persists, the harness must be at fault.
- Other Troubleshooting Tips: If you have a T.V. raster only
  (a T.V. raster is a blank, but lit T.V. screen with the brightness
  turned all the way up) and you want to determine if it is the
  PCB or the T.V. that is causing the lack of video display, try
  the following test: (A)disconnect the PCB edge connector;
  (B) turn the brightness and contrast all the way up; (C) connect
  pin 11 of the PCB edge connector to pin 12 with a test lead. If

your T.V. monitor is functioning correctly, you will see faint black bars ("hum bars") on the screen.

TO CHECK THE SPEAKER, turn the colume control all the way up, and connect one end of a test lead to pin 2 (audio) of the disconnected PCB edge connector. Momentarily touch the other end to either pin 3 or pin 4 (transformer secondary AC) of the edge connector and if the speaker is functioning correctly, you will hear a loud buzz (60 cycle hum). To check if the TV POWER SUPPLY is functioning correctly, use the following procedure: check the T.V. power supply output between pin 6 and pin 8 with a VOM. Meter should read 5 volts DC.

### Troubleshooting by Symptom:

- NO POWER: a. check for correct line voltage and if OK then check fuses and interlock switches. If OK, check transformer primary which should show line voltage. Then check transformer secondary (pins 19 and 21) which should be 10 VAC.
- 2. GAME CREDIT SHUTS OFF: Try cutting the antenna wire shorter in increments of 1-2 inches.
- 3. GAME CREDIT SHUTS OFF AND/OR T.V. PICTURE SHRINKS: Check line voltage with VOM and be aware that a large motor nearby (e.g. air conditioner) may drop line voltage when starting up.
- 4. NO PICTURE; NO RASTER: Check to see if T.V. connector is plugged in; check for line voltage at T.V. and if T.V. AC voltage switch is set to correct position. Check T.V. fuses and brightness control.
- 5. T.V. RASTER ONLY: Check harness and especially the PCB edge

- connector. Check PCB. Check T.V.
- 6. PICTURE ROLLS: Adjust T.V. vertical hold. Check or replace PCB.
- PICTURE IS WAVY: Adjust T.V. horizontal hold. Replace transformer. Check harness, particularly grounds.
- 8. PICTURE IS BROKEN INTO DIAGONAL LINES: Adjust T.V. horizontal hold. Replace PCB.
- 9. JERKY PLANE MOTION: Replace appropriate potentiometer.
- 10. NO GAME CREDIT: Check coin switch and harness. Replace PCB.
- 11. GAME SEQUENCE INCORRECT OR PARTS OF PLAYFIELD DISPLAY MISSING,
  DISTORTED OR NOT FUNCTIONING: Replace PCB.
- NO AUDIO: Check volume control, speaker connections.
   Replace PCB.

#### DIAGNOSIS:

SYMPTOM	CHECK

No picture Power cord, harness connections,

line and monitor fuses.

No sound Speaker connections, volume adjustment

Rolling or tearing picture Readjust T.V. controls

White picture but no display Edge connector on logic PCB, 5 volt

supply from monitor, 12 pin Molex

connector on monitor.

Wavy Picture 5 volt supply, 73 volt regulator

adjustment


Game will not start Coin mechanism, harness connections

No Firing Joystick, harness connections

NOTE: If the above checks do not solve the problem, consult the appropriate theory of operation description of the logic PCB circuits.

## M. P.C.B. SHIPPING

Careful packing of PCBs and other parts being returned is recommended as we cannot be liable for items damaged in transit. If possible, include a short statement describing the problem encountered with the game.



35

#### ASSEMBLY TITLE PURSUIT CABINET FINAL ASSY PARTS LIST SPECIFICATION -1/--, / Drawn Checked Proj. Eng. 11 - where Elec. Eng leisure Rev. Description Date Apprv. Rev. Description Production Release 12-27-74HW Per FCN = 1028 Rev per ECN 1054 12-27-74-1-13-75

P/L A002869

REV.

С

Apprv.

Page 1 of 1

Date


Item	Part Number	Qty.	DESCRIPTION
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 22 23 24	A002869 A002804 A002882 A002870 A002871 A002780 A002878 73-7401 75-5520N 75-015S 75-015S 75-0146 75-0146 75-040 A002807 A002808 A002879 75-2124S 75-911S 75-014C 75-050 75-7606	Ref 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Cabinet Final Assy Cabinet Upper, Formed Panel Assy Flourescent Light Assy T.V. Mounting Assy Joystick Assy Double Coin Switch Assy Southco Rivet #38-106-30-13 Carriage Bolt 1/4-20 x 1-1/4 Plain Washer 1/4" Lock Washer 1/4" Hex Nut 1/4-20 Carriage Bolt #10-24 x 2" Hex Nut #10-24 Plain Washer #10 Lock Washer #10 Harness (Sub) Harness (Main and Sub) PCB Tray Assy R.Hd. Mach. Screw #10-24 x 1-1/2 Hex Nut #10-24 Flat Washer #10 Lock Washer #10 Sht. Metal Screw Pan Hd. Phil. #6 x 1"

36

<b>,</b> -1		ASSE	MBLY .	FLUTE		PURSU	ΙΤ	d 				P/L	00	2490
$-\mathcal{J}$					TS LIS	ST SP	ECIFI	CATI	ON			Page	1 0	f 3
الأحميا	( 65	Draw	70.000000000000000000000000000000000000	12		1-12-7								- North Assessment
Nir		Chec		• , •		*		Mech	. Eng.				· · · · · · · · · · · · · · · · · · ·	,
Innov	DILLAC		. Eng	(Carrier 1977)	· ·	12 - 12 12 - 12		Elec	. Eng				/	REV
16130		<u> </u>	4	念	11	2/1							3	0
Rev.	Description				Appro		v.	Des	cripti	on	2555	Dat	te	Αρρτν.
BC	PAROLLI. Rev per ECN 1	021 1/		-17-74	V ~		_		Heliopeid					
	& 1035		11-	8-75-	2.1	<del>,3</del> —		1 to 2015 MI AND	- 35		- SEPTEMBER 1	-	-	
C	REM FEG. FONT	057. TO	212	- Y.(( <sub>*</sub>	Fig.	Z								
			+		<del> </del>	<u></u>			- 12	-				-
4.50						-j		***		G 50 5				
ltem	Part Numbe	r	Qty.		<del>-</del>		DES	SCRTI	"I LON	100.000	Polon San		5401 5401 577520 - 77774	<del></del>
1	37-7400		10		7400		ja (-		79,2	- is 28 - 190				
2	37-7402 37-7404		5 9		7402 7404									
3 4	37-7404		4		7405									
5	37-7406		2 5 3		7406									
5 6 7	37-7410 37-7420		5		7410 7420									
8	37-7427		2		7427									
9	37-7442		1		7442									
10	37-7474		13		7474 7486		28							
11 12	37-7486 37 <b>-</b> 7493		13		7493									
13	37-74107		4	I.C.	7410	)7								
14	37-74132		]		7413									
15 16	37-74153 37-74164		2		7415 7416									
17	37-74193		4	I.C.	7419	33								
18	37-74279		3		7427	9								
19 20	37-555 37-741		2		555 741									
21	37-LM339		1	I.C.	LM33									
22	37-LM324		ļ		LM32									
23 24	37-3080 37-LM309K		1		, 3080 , LM30									
25	37-LM380		i	I.C.	. LM38	30								
26	10-02P7		1	Res	istor,	, 27	ohm,	1/4	watt,	10%	R125			
27 28	10-0220		1		н	22	11	н	10	10	R101			
29	10-0220		1		D	100	11	11	11	11	R120	, e		
30	10-0181		2	ľ	ti ti	180	11	H H	11		R37,54			
31	10-0221		2 2		H H	220 330	11	11	п		R39,86 R39,R4			
32 33	10-5331 11-5331		1		10	330	Ü	1/2	11		R112	s≅		
34	10-0331		3		16	330	и	1/4	U 61	108	R3,R2	10 DF	מם פר	A AT
35	10-0471		8		11	470	**	11	ff		R97,R0			4,81,
36	10-0561		4		11	560	ij	11	10		₹79,94	,60,67	7	
37	10-0102		14		11	1K	9	н	н		107,38			
	1		1	į.			н	11	ü		28,1,18 221,23	,,,,,,	,10	1,144
38	10-0563		2 7	į.	111	56K		1000			161.63	13		170.000

ASS	EMBLY TITLE PURS	UIT	P/L 002490
	PARTS LIST	SPECI	FICATION Page 2 of 3
Item	Part Number	Qty.	DESCRIPTION Rev D
39	10-0222	5	Resistor, 2,2K ohm, 1/4 watt,10%, 92, ,16, 9,108,105
40	10-0272	10	" 2,7K " " " R31,41,42,74,95, 35,36,17,32,100
41 42 43	11-5221 10-0392	1 1	" 220 " 1/2 " 5% R113 " 3 9K " 1/4 " 10% R119
44	10-0472 10-0562	3 5	" 4.7K " " " R93,102,103 " 5.6K " " " R47,91, ,118
45 46	10-0682 10-0822	1 1	" 6.8K " " " R11 " 8.2K " " " R117
47	10-0103	8	" 10K " " " R87,83,106,96,98, 99, 43,73
48 49	10-0153 10-0223	4 3	" 15K " " " R68,19,22,59, " 22K " " " R13,R24,R26
50	10-0333	5	" 33K " " " R25,48,52,12,20
51 52 53	10-5563 10-0823 10-0104	2 1 5	" 56K " " " 5% R46,R44 " 82K " " "10% R53 " 100K " " " R29,30,51,77,121
54 55 56 57 58 56 66 66 66 67 67 77 77 77 77 77 80 81 82 83	10-0154 10-0474 10-0394 10-0564 10-0684 10-0125 10-0225 10-0395 34-2N3643 34-2N3644 31-1N4001 27-120104 29-008 27-250104 27-101103 29-009 21-101224 28-101221 28-101221 28-10101 24-250475 24-250106 24-250507 24-060107	2 2 2 2 1 4 2 2 2 2 1 6 © 5 7 2 3 6 3 2 1 1 1 4 3 1 1 1 1 1 1	" 150K " " " R7,R8  " 470K " " " R83,34  " 390K " " " R50,76  " 560K " " " R122,R14  " 680K " " " R4  " 1 meg " " " R53,65,6,5  " 1,2 " " " R64,66  " 3,9 " " " R62,61  Transistor, NPN, 2N3643  " PNP, 2N3644  Diode, 1N914  Diode, 1N4001  Capacitor, .luf, +80%,-20% Ceramic C15,16,9,3,25,  " +20%, 12 volts,C24,C28  " +80%,-20%,Cer,C17,1,30,35,15,14  " .00luf,±10%,100v,C32,C11,7  " .22uf,±10%,Mylar, C31,29  " 220pf, Ceramic Disc,10%,C5  " 100pf, Ceramic Disc,10%,C5  " 10uf,25v,Electrolytic,C10,33,34,18  " 1uf,25v, Electrolytic,C44,36,37  " 50uf, 25v, Electrolytic,C40  " 500uf, 25v, Electrolytic,C40
85	19-311105	ī	Pot, 1 meg, CTS x201 R105B

ASSI	EMBLY TITLE PUR	SUIT	- Weight - 1872	P/L 002490
·	PARTS LIS	ST SPECI	FICATION	Page 3 of 3
tem	Part Number	Qty.	DESCRIPTION	Rev D
85 86 87 88 89 91 92 93 94 95 96	19-311502 19-311104 66-02 19-311251 002743 75-26018 75-0168 75-9168 12-0101 38-MV5013 10-0274	Qty. 4 1 1 2 2 2 2 1 1 1	Pot, 5K, CTS x201R502B Pot, 100K, CTS x201R104B Dip Switch, Molex 4130 #07 Pot, 250 Crystal 12.096 MHz Screw, 6-3? x 5/8", Pa Washer, Internal Star Washer, Flat Nut, Hex, 6-32 Resistor, 100 ohm, 1 watt, LED, MV5013 Resistor, 270 K ohm, I/4 w	1-70-0104 n Hd., S.S. Lock, #6



SYM	DESCRIPTION	DETO	APPV.
~	REV PER ECN 1021,1034,1035	44/9	נוע אַ
D	BEN PER ECH 1057, 1672	R Ya	HUSE

#### MODIFICATIONS:

- I. CHANGE REO & REOT FROM S. GK TO SEO. R.
- 2. ADD INADOL BETWEEN + ISV & +SV , CATHODE TO + ISV .
- 3 ADD LED IN SERIES WITH BOOM RESISTOR BETWEEN HEV & GUD.
- 4. DELETE 1, C. AB (7493).
- 5. JUMPER PIN 1 TO PIN 14 ON AS 1.C. PATTERN.
- 6. CHANGE RIS FROM 2.2K TO IK.
- 7. ADD 100.0, I'W RESISTOR IN EXISTING HOLES NEXT TO CRIZ.
- B. DELETE HEATSINK FROM LM309.
- 9. DELETE THE FOLLOWING COMPONENTS:
  - A. C43 250MF
  - B. Q17 2N36A3 C. CEIO - 1N914
  - D. CEII 14001
  - E, CR8 14514
  - F. RIK IK
  - 6. 2114 15.A H. 2118 - 1002
  - I. LID RELAY
- IO. ADD JUMPER BETWEEN WIPER AND N.C. OF RELAY PATTERN.
- 11. ADD 270K RESISTOR FROM MB PING TO C.W. SIDE OF LOOK POT.
- 12. CLIT TRACE, AS SHOWN, ADJACENT TO KS & LS. RUN JUMPER FROM TRACE TO 1.C. LG PINS.
- 13. JUMPER LEADS OF RIZI & RIZZ NEAREST LOOK POT.

KEP-A PURSUIT REV. D

KEE GAMES INC. ASSY.

14600 WINCHESTER BLVD.

LOS GATOS CA. 95030


(408) 374-2440


SCALE: 1/1 APPROVED:


DATE: 11-7-74

P. BRISTOW


DRWG. NO. A002490









· Purkula	PHEREFI	APP
1.00	115175	7
	-	PRAWN CHECKED





42



SIDE VIEW

ECW 1083 1-22-75 H.W.46 1-22-75 P.W.46

	<b>200</b> 4	છે. કેર્યું <u>'</u>	
-13		CHAIN-STL. SINGLE JACK #12	4
-/2		COTTER PIN 1501A X /21.	=08
-11		14-20 ×1 CARKIAGE BOLT	2
		M LOCK WASHER	2
-10		#-20 HEX NUT	2
-9	C02784	NINTO PLATE	1
14	A11 - 6606A44	LOCK WASHER - 5/16	2
-6		HEX NUT 5/0-18	2
-7	0092-053	SHEET METAL SCREW 6x4L	4
	002809	STOP	1
.5	1002781	KRAFT JOYSTICK MODIFICATION	1
	002786	BRACKET	1
- ź	J:	CARRIAGE BOLT 5-18×1	2
-1	4002783		1
	DIVG - NO-	DESCRIPTION	X 74

KEE GAMES

BARTIE - 11 /4 20 - 12/1/11 BENEED 1/15/15

PURSUIT

FINAL ASS'X- JOY STICK ADOZTAO