SONY®

Data Projector

取扱説明書(ネットワーク編)	JP
Operating Instructions for Networking	GB
Instructions en cas de mise en réseau	FR
Manual de instrucciones de red	ES
Bedienungsanleitung für das Arbeiten im Netzwerk	DE
Manuale di rete	IT
网络用使用手册	CS

お買い上げいただきありがとうございます。



ソフトウェア製品は、安全のための注意事項を守らな いと、健康を害することがあります。

この取扱説明書には、健康を守るための重要な注意事項と製品の取り扱いかたを示してあります。この取扱説明書をよくお読みのうえ、製品を お使いください。お読みになったあとは、いつでも見られるところに必 ず保管してください。

VPL-PX15 **VPL-FX51**

Table of Contents

Before Using	Features Precautions About This Manual	6 (GB)
Preparation		
	Preparations for Using the Networking	Function 7 (GB)
	System Configuration	
	Using the PC Card	
	Setting for Networking Function	
	Using the Remote Commander	
	Using the Net Mouse Function	
	Setting Up the Projector	
	Setting the User Information	
	Setting the System	
	Setting the Date and Clock	10 (GB)
	Setting the On-board LAN	10 (GB)
	Setting Up a Wireless LAN Environment	
	— when a zero configuration card is u	sed 11 (GB)
	Setting Up a Wireless LAN Environment	
	— when a VAIO or ORiNOCO wirele	
	card is used	
	Setting the Password	13 (GB)
	Assigning an Application Software to the	
	on the Remote Commander	-
	Setting Up from a Computer	
	Basic Operation Flowcharts	
	Operations from the Projector	
	Operations from a Computer	
Operation		

GB

eralion

.....

Operations from the Projector	20 (GB	3)
Preparations	20 (GE	3)
Running a Presentation of a PowerPoint File Using		
the Slide Viewer	21 (GE	3)
Projecting an Excel File Using the Worksheet Viewer	or	
Word File Using the Document Viewer	23 (GB	3)

(continued)

· Microsoft, Windows and PowerPoint are the registered trademarks of Microsoft Corporation in the United States and/or other countries.

• All other product and company names mentioned herein are trademarks or registered trademarks of their respective owners.

• ORiNOCO is a registered trademark of Proxim Corporation.

	Running a Slide Show Using the Image Viewer	25	(GB)
	Connecting to the Internet	27	(GB)
	Using the Remote Desktop Function	27	(GB)
Ор	erations from a Computer	28	(GB)
	Preparations	28	(GB)
	Starting the browser for accessing the projector	28	(GB)
	Accessing the projector using the Auto Projector Sear	ch	
	function	28	(GB)
	Running a Presentation of a PowerPoint File Using		
	the Slide Viewer	29	(GB)
	Projecting an Excel File Using the Worksheet Viewer		
	or Word File Using the Document Viewer	32	(GB)
	Projecting an Image Using the Image Viewer	34	(GB)
	Using File Manager	37	(GB)
	Controlling the Projector from a Computer	38	(GB)

Others

Maintenance Function	39 (GB)
Checking the Indicators on the Projector	
— when operating from a computer	39 (GB)
Using the e-Mail Report Function	39 (GB)
Troubleshooting	43 (GB)

The projector is compatible with networking. Connecting to a Local Area Network (LAN) allows you to run a presentation using a file stored in a computer connected by the same LAN. You can open the file from a computer located far away from the projector as well as one in the same conference room. Connecting to the Internet only with the projector is also available.

When you have access to the projector by using the Web browser of a computer, you can control the projector from that computer.

Connection to a LAN

The projector is equipped with the ETHER connector and a PC card slot, which allows you to connect the projector to LAN by using the LAN cables. Installing a wireless LAN PC card to the PC card slot enables wireless LAN connection.

Presentation Viewer

The projector has built-in simple Microsoft PowerPoint, Microsoft Excel and Microsoft Word viewer funtions, named Slide Viewer, Worksheet Viewer and Document Viewer, respectively. The functions allow you to run a slide show using a PowerPoint file or to project an Excel or Word file without any conversion.

Image Viewer

The projector has built-in Image Viewer function, allowing you to view images created in the JPEG, BMP, GIF or PNG format, to set up a slide show, and to run a slide show using the images.

Remote Desktop

This projector is compatible with the Remote Desktop feature incorporated in Windows XP Professional. The projector can access a computer on the same LAN, allowing projection of any file stored on that computer, as if it were in front of you.

Web browser built-in

The Internet Explorer 5.5 or its equivalent is built into the projector, allowing you to connect to the Internet.

Auto Projector Search function

If Windows Me or Windows XP is installed in your computer, you can easily get access to the projector's Web browser by double-clicking the corresponding projector's icon in the My Network window of the computer. You can promptly start a presentation.

Net Mouse function

This function allows you to operate the projector for setup, run a presentation, etc. with the mouse and keyboard of a computer by displaying the projector window on the computer.

File Manager

Use of a computer's Web browser enables you to add files stored in the computer to the projector or delete files stored in the projector by operating the computer.

Projector information via web browser

You can check the present status of the projector and version information of the projector on the computer display.

e-Mail Report function

The projector enables the sending of mail that contains the time of replacement of the projector lamp, error occurrence, etc., to the mail addresses that have been specified.

SNMP available

When an SNMP (Simple Network Management Protocol) is used for the network management, you can also manage the projector by the SNMP.

Memory function

The projector can store a file imported from a computer or a memory card.

When you store the file, you can create a password to prevent unauthorized people from opening it.

PC card slot incorporated

The projector is equipped with a PC card slot. Inserting the PC memory card, in which data are stored, into this slot allows you to run a presentation easily without using a computer.

About This Manual

Caution

Before you turn off the projector or reset it by using the supplied Remote Commander, make sure to exit any application software which is running. Otherwise, system damage may occur and you may not be able to restart the network function.

- Recommended system requirements for the projector are as follows:
- Microsoft Windows 98, Microsoft Windows 98 SE, Microsoft Windows 2000, Microsoft Windows Me, Microsoft Windows XP Professional
- Suitable browsers are Internet Explorer 5.0 or later versions.
- The viewers of the projector are compatible with PowerPoint, Excel and Word of Windows Office 97 and 2000. However, some features of the applications may not be correctly displayed.
- Make sure to use the specified/recommended wireless LAN PC card and PC memory card. Also use the specified/recommended wireless LAN PC card to install into the connected computers.

Using a device not specified/recommended may cause incorrect operations.

For the specified/recommended devices, see the supplied "Specified/recommended PC Card."

- To prevent data loss, make backup of data frequently. In no event will Sony be liable for any loss of data.
- Please note that the software specifications are subject to change without notice.
- Some of the illustrations in this manual may differ from the actual application software.

This manual explains networking operations of the VPL-PX15 and VPL-FX51 Data Projector. On-line Help files are also available. When you access the Web server of the projector, a Help sentence will appear on a computer when you rest the pointer over each item.

You can open the help file of the network projector by clicking Help from the Start menu on the desktop. However, some network features are not supported by the projector. The Help file for Slide Viewer, Worksheet Viewer, Image Viewer or Document Viewer opens when you click the № button on the tool bar of the respective application window.

Refer to the Operating Instructions of this model for operations other than networking.

About the supplied software

The projector furnishes the software and the accompanying documentation of Sony and its licensors.


- It is prohibited to modify or disassemble the software or the accompanying documentation, in whole or in part, except permission. In addition, it is prohibited to transfer, license or disclose the software, or the accompanying documentation, in whole or in part, to any third party except permission. Finally, it is prohibited to use the software and the accompanying documentation, in whole or in part, on any product or system other than the projector.
- Sony and its licensors do not warrant that the software or the accompanying documentation will meet your requirements or that the operation of the software will be uninterrupted or error free.
- Sony and its licensors will not be liable, and you will have no remedy for damages for any claim of any kind whatsoever, concerning your use of the software or the accompanying documentation, regardless of legal theory, and whether arising in tort or contract. In no event will Sony or its licensors be liable to you for any special, indirect, incidental, or consequential damages of any kind, including, but not limited to, compensation, reimbursement or damages on account of the loss of present or prospective profits, loss of data, or for any other reason whatsoever concerning your use of the software or the accompanying documentation.
- Software specifications are subject to change without notice and may not necessarily be identical to current retail versions.

This section describes the tasks that are required for using the networking function of the projector.


System Configuration

For details on connections, refer to the Operating Instructions of the projector.







Connecting to wireless LAN using the wireless LAN access point



Connecting to wireless LAN without using the wireless LAN access point (Peer to Peer mode)



Using the memory card



Using the PC Card

The PC CARD slot of INPUT B (VPL-PX15) or INPUT C (VPL-FX51) on the projector accepts one PCMCIA Type II PC card. To connect to a LAN, it is necessary to insert the specified/recommended wireless LAN PC card into this slot. You can also insert the recommended PC memory card into this slot. Storing the file created with Microsoft PowerPoint, Excel or Word, or the image file in a memory card enables you to project a file or run a presentation without connecting to a computer.

Notes

- Do not turn off the projector or restart the network projector while the PC card is writing or reading.
- Be sure to use the specified/recommended wireless LAN PC card or PC memory card. For the specified/ recommended cards, see the supplied "Specified/ recommended PC Card."
- The driver software for the specified/recommended PC cards is installed into the projector at the factory. Installing any other driver software is not required and cannot be done.

For inserting and removing the PC card, refer to the Operating Instructions of the projector.

Setting for Networking Function

To activate the networking function of the projector, do the following setup.

■ For VPL-PX15

Set INPUT-B FUNC. in the INSTALL SETTING menu to ON.

For detailed information, see the Operating Instructions of the projector.

■ For VPL-FX51

Set INPUT-C FUNC. in the INSTALL SETTING menu to ON.

For detailed information, see the Operating Instructions of the projector.

Using the Remote Commander

When you operate the projector for setting up the projector, running a slide show, etc., use the supplied Remote Commander. Before operation, set the PJ/ NETWORK select switch on the Remote Commander to NETWORK. You cannot connect a mouse and keyboard to the projector.

Using the Net Mouse Function

When you operate the projector for setup, type an Internet address, run a presentation, etc., you can do so by operating the mouse and keyboard of a computer.


Note

Only Internet Explorer Version 5.0 or later is available for using the Net Mouse function.

Start the Internet Explorer Version 5.0 or later on the computer.

2 Enter the IP address of the projector. Type "http://xxx.xxx.xxx (IP address of the projector)/netmouse".

The window of the projector appears on the computer.



3 Operate with the mouse of the computer within the projector window displayed on the computer. The operations of the mouse and keyboard reflect those on the projector screen and you can operate the projector.

Note

When the network environment is heavily loaded, movement of the mouse on the projector may not be smooth. Basic setups such as IP address and wireless LAN settings are necessary for networking operations of the projector. You can set them up either from the projector or a computer connected to the same LAN.

Before setting up


- Turn on the projector with the I/\bigcirc key on the supplied Remote Commander or control panel of the projector.
- Confirm that INPUT-B FUNC. (VPL-PX15) or INPUT-C FUNC. (VPL-FX51) in the INSTALL SETTING menu is set to ON.
- Press the INPUT key on the supplied Remote Commander or control panel of the projector to select INPUT B (VPL-PX15) or INPUT C (VPL-FX51). The Network Projector window opens.
- Set the PJ/NETWORK select switch on the Remote Commander to NETWORK.
- When you are setting up the items from the projector, using the Net Mouse function is convenient. *For details on the Net Mouse function, see page 8 (GB).*
- You can also set up from the projector using the screen keyboard displayed on the projector's screen, and operate with the supplied remote commander. *For information on the screen keyboard, see page 21 (GB).*

Setting the User Information

You have to set the user and projector information. This information is used for the e-mail Report function.

- **1** From the Start menu, click Control Panel in the Network Projector window.
- **2** Double-click the User Information icon. The User Information Properties dialog box appears.

3 Click the User tab and input Name and Organization.



4 Click the Projector tab and input Location, Installation, Lens, and Memo.

		on
		tor Location Here
~	Lens: Standard	lation: FLOOR-FRONT 🐱
1	Lens: Standard	

Setting the System

You have to set the projector name for identification in the network configuration.

- **1** From the Start menu, click Control Panel in the Network Projector window.
- **2** Double-click the System icon. The System Properties dialog box appears.
- **3** Click the Projector Name tab and input Name and Description.

System Proper	ties	? OK
General Memo	y Projector Name Copyrights	
് സ് സ	ese settings are used to identify your P nputers, se type a name (without any spaces) Name: VPL-PX15	-
De	scription: Sony Network Projector	

Setting the Date and Clock

The clock is displayed on the task bar of the Network Projector window. To set the date and time, follow the steps below.

- From the Start menu, click Control Panel in the Network Projector window.
- **2** Double-click the Date/Time icon.
- **3** Set the date and time.

Setting the On-board LAN

Setting up the network configuration, such as IP address setting, is necessary for building a LAN connection. The IP address of the projector will be displayed on the task bar of the Network Projector window of the projector.

If the connection environment is changed, you need to set up the network configuration again.

- **1** From the Start menu, click Control Panel in the Network Projector window.
- **2** Double-click the Network Connections icon. The window appears and the available network icons are displayed.
- **3** Double-click the On-board LAN icon. The On-board LAN settings dialog box appears.
- **4** Confirm that the "Specify an IP address" radio button is selected, and set the necessary items. The IP Address is initially set to "192.168.0.1," and the Subnet Mask is set to "255.255.0.0" at the factory.

LAN' Settings	No. of Concession, name	ОК 🗙
Name Servers		
ess can be	O Obtain an IP ac	ldress via DHCP
If your network	() Specify an IP a	ddress
	IP <u>A</u> ddress:	192.168.0.1
or for an address,	S <u>u</u> bnet Mask:	255.255.0.0
and then type it in the space provided.	Default <u>G</u> ateway:	
	Name Servers ess can be ally assigned to this If your network utomatically assign es, ask your network or for an address,	Name Servers ess can be If your network asy asky your network or for an address: Sybeit in the space IName Servers O Obtain an IP ac O Specify an IP a IP ≙ddress: Sybnet Mask: Sybnet Mask:

5 Click the Name Servers tab to display the Name Servers dialog box, then set the necessary items.

P Address Name Servers				
Name server addresses may be	Primary <u>D</u> NS: [4	
automatically assigned if DHCP is enabled on this adapter.	Secondary D <u>N</u> S: [
'ou can specify additional VINS or DNS resolvers in the	Primary <u>W</u> INS: [1	1	1
space provided.	Secondary WINS:		- 89	

6 Click the OK button. The window in step 2 reappears.

When you use a wireless LAN PC card Follow the steps below.

- 1 Click the right button of the mouse on the On-board LAN icon.
- **2** Click "Disable".

When you want to use On-board LAN, click "Enable".

Setting priority of On-board LAN and wireless LAN

When priority is set, the connection is automatically selected according to priority and you do not need to set "Enable"/"Disable". The second connection is selected when the first connection is disconnected.

1 Click Advanced on the menu bar. The Advanced setting window appears.

2 Set priority in the Advanced Adaptor Settings window.

Setting Up a Wireless LAN Environment — when a zero configuration card is used

Set up IP address, Name servers and Wireless Networks.

- **1** From the Start menu, click Control Panel in the Network Projector window.
- **2** Double-click the Network Connections icon. The window appears and the available network icons are displayed.
- **3** Double-click the icon of the Wireless LAN. The settings dialog box appears.
- **4** Confirm that the "Specify an IP address" radio button is selected, and set the necessary items. The IP Address is initially set to "Obtain an IP address via DHCP" at the factory.
- **5** Click the Name Servers tab to display the Name Servers dialog box, then set the necessary items.
- **6** Click the Wireless Networks tab to display the Wireless Networks dialog box and click the access point to be connected.

Jse <u>W</u> indows to configure r	ny wireless network settings
ailable <u>n</u> etworks:	
o connect to an available ne	
0a3251 0a4479	<u>Configure</u>
1 Ud99/9	
P Oadb92	Refresh
eferred networks:	lable networks in the order listed
• eferred networks: utomatically connect to avai	
• eferred networks: utomatically connect to avai elow:	lable networks in the order listed

7 Click the OK button.

Setting Up a Wireless LAN Environment — when a VAIO or ORiNOCO wireless LAN PC card is used

Set up IP address, Name servers and Wireless Networks.

Using a wireless LAN access point

Set up the access point you are connecting to as follows.

- **1** From the Start menu, click Control Panel in the Network Projector window.
- **2** Double-click the Wireless LAN icon. The Wireless LAN settings dialog box appears.

Wireless LAN	settings	? Ok	$ \times$
Select Profile -			
	Nickname		
Default	:		1
0			1
0			1
0			1
			7
		Edit	

3 Click the radio button for Nickname, and type a nickname in the selected text box.

4 Click the Edit button.

The Access Point settings dialog box appears.

Access Point s	ettings 🛛 ? OK 🗙
Basic	
<u>N</u> ickname:	Default
Access Point ID:	ANY
Encryption Key:	
<u>P</u> eer to Peer:	

5 Enter a Nickname.

The Nickname identifies the access point. Enter up to 32 characters for the Nickname using alphanumeric characters and symbols (ASCII characters). If multiple access points exist, make sure to assign a different name to each one.

(continued)

- **6** Enter the Access Point ID. Type the ID specified for the access point you are connecting to.
- 7 Enter the Encryption Key. Type the encryption key, if it is set and is active on the access point.
- **8** Click the OK button. The Wireless LAN settings dialog box reappears.

Click the radio button of the Nickname you want 9 to use, and click the OK button. Connection is made to the selected access point.

To connect to an access point which is already configured

If multiple access points exist, you can assign up to four Nicknames for them. If you want to connect to an access point which is already configured, select a radio button next to the relevant Nickname then click the OK button in the Wireless LAN settings window. Connection is made to the selected access point.

Note

When the manufacturer of the wireless LAN card inserted into the projector and that of the wireless LAN access point are not the same, how to enter the encryption key may differ. If the encryption key appears in hexadecimal values, enter the hexadecimal values for Encryption Key.

When no communication is taking place between the access point and the projector

If the channel for the access point is set to 12–14, set it to any channel between 1 and 11.

Notes

- Contact qualified Sony personnel if any trouble occurs when you are using the specified/ recommended Sony wireless LAN PC card.
- If the manufacturer of the wireless LAN card and that of the wireless LAN access point are not the same, communication by enabled encryption does not take place correctly.

Peer to Peer (Ad-hoc) mode

To connect to a wireless LAN between the projector and computers without using the wireless LAN access point, follow the steps below on the projector only.

- **1** Follow steps **1** to **5** in "Using a wireless LAN access point." In the Access Point settings dialog box, set the Nickname of this mode.
- **2** Click the checkbox next to Peer to Peer.
- **3** Enter an optional Access Point ID. You can type up to 32 alphanumeric characters for the ID.
- 4 Enter the Encryption Key if you want to make it active.
- **5** Click the OK button. The Wireless LAN settings dialog box reappears.
- **6** Click the radio button of the Nickname you entered in step **1**. The Peer to Peer mode takes effect.

For the computers connected it is required to enter the same Access Point ID and Encryption Key as those entered in the procedure above and an optional Nickname. For details, refer to the Operating Instructions of the wireless LAN PC card inserted into the computers.

Notes

- Use wireless LAN PC cards of the same manufacturer both for the projector and the computer.
- If Peer to Peer (Ad-hoc) is configured on one of the connected computers, perform step 1, then steps 3 to 6 above to enter the same Access Point ID and Encryption Key as those of the computer and an optional Nickname on the projector.
- Select Peer to Peer (Ad-hoc) only for one of the projector and computers on the same LAN.
- When you use Peer to Peer (Ad-hoc) mode, you need to set a dedicated IP address and Subnet Mask for this mode on the projector and the computer.


Setting the Password

You can set a password for protection against access from remote network users.



From the Start menu, click Control Panel in the Network Projector window.

2 Double-click the Password icon. The Password Properties dialog box appears.



3 Specify the Password for Administrator, then enter the same password again in the Confirm password text box for Administrator.

The Name of Administrator is preset as "root" at the factory. It cannot be changed.

4 Specify the Name and Password for User, then enter the same password in the Confirm password text box for User.


When you are required to enter the password for Administrator or User while you are operating the projector from a computer, enter the Name and Password which you set in steps **3** and **4**.

Assigning an Application Software to the FUNCTION Key on the Remote Commander

If you assigned an application to the FUNCTION 1 or 2 key on the supplied Remote Commander, a touch of the key enables you to start that application. The screen keyboard is assigned to the FUNCTION 3 key at the factory, and you cannot reassign or cancel that assignment.

For detailed information about the screen keyboard, see page 21 (GB).

- **1** From the Start menu, click Control Panel in the Network Projector window.
- **2** Double-click the Launch Keys icon. The Launch Keys Settings dialog box appears.



- **3** Click Browse for the key (1 or 2) to which you want to assign an application software, then click the application you want from the application list.
- **4** Repeat step **3** if you want to assign an application to the other key.
- **5** Click the OK button.

Setting Up from a Computer

When you want to type letters using a keyboard, set up from a computer.

Notes

- Connect a single computer you are using for setups to the projector if the IP address of the projector is not changed from the factory-preset one.
- If the browser of your computer is set to "Access the Internet using a proxy server," enter the IP address of the projector in the box "Access the Internet without using a proxy server" when you have access to the projector from your computer.
- The computer may not accept the password for the projector, depending on the version of the browser. In this case, restart the browser.

Opening the setup window

- **1** Start the computer's browser software (Internet Explorer 5.0 or later).
- 2 Type "http://xxx.xxx.xxx (for the IP address of the projector)/setup".
 If the IP address is not changed from the factory-preset one, type "http://192.168.0.1/setup" (When using On-board LAN).
 If the number of the IP address starts from 0 (zero), enter the number without 0.
 Example: 192.168.000.001 → 192.168.0.1
 - The Password dialog box appears.

3 Enter the Name and Password for Administrator. If the Password setting is not changed from the factory-preset one, enter "root" in the Name text box.

The Setup window appears.

Sony Network	Projector
Setup	
	User System Network Password Uniternative Report
——	anakanasuka. Ugaldat magalat
l ——	

- 4 Click the icon to be set up. Set up the items in the same way from the projector.
- **5** Click the APPLY button.

Basic Operation Flowcharts

This section describes the operation flowchart for using the projector via a network or for using the builtin network function of the projector. There are two types of flowcharts; for operations from a computer and for those from the projector. For details, see the pages in parenthesis.


Required conditions

- The projector and computer are connected to the same LAN.
- The projector and computer are turned on.
- The INPUT-B FUNC. (VPL-PX15) or INPUT-C FUNC. (VPL-FX51) is set to ON in the INSTALL SETTING menu.
- The input of the projector is set to INPUT B (VPL-PX15) or INPUT C (VPL-FX51).

Operations from the Projector


Running a presentation using a file stored in the computer

Immediately after you open a file created with PowerPoint stored in a computer, you can start a presentation by operating the projector.




Running a presentation using a file stored in the projector or memory card

By using a PowerPoint file stored in the projector or in the PC memory card, you can run a presentation by operating the projector only.




Projecting an Excel or Word file stored in a computer

You can project an Excel or Word file stored in a computer on the same LAN by operating the projector.




Projecting an Excel or Word file stored in the projector or memory card

You can project an Excel or Word file stored in the projector or memory card onto the projector.




Running a slide show using an image file stored in the projector or memory card

You can run a slide show using an image file stored in the projector or memory card by operating the projector only.



Connecting to the Internet




Running a slide show

Operations from a Computer

Projecting an Excel or Word file onto the projector


You can display an Excel or Word file on the projector by operating from a computer.

d file onto theProjecting an image onto the projector
using a file stored in a computerfile on the projectorYou can project an image onto the projector by
operating from a computer.



Projecting an image or running a slide show onto the projector using a file stored in the projector

By using an image file stored in the projector or in the PC memory card you can project it on the projector by operating a computer. You can also run a slide show using the slide show setting file preset on the projector.



Managing files with File Manager

You can add files stored in a computer to the

projector's storage or delete files stored in the

[When using the Auto

Projector Search

function1

projector.

Starting a Web browser

of a computer to access

19 (GB)

Adjusting or setting the projector

Preparations

Before starting

- Confirm that INPUT-B FUNC. (VPL-PX15) or INPUT-C FUNC. (VPL-FX51) in the INSTALL SETTING menu is set to ON.
- Using the Net Mouse function allows you to operate the projector screen with the mouse and keyboard of the computer.

For details, see "Using the Net Mouse Function" on page 8 (GB).


• When you use the supplied remote commander, switch the PJ/NETWORK select switch to NETWORK.

Opening the Network Projector window

To perform networking operations without connecting to a computer, display the Network Projector window on the projector.

- **1** Turn on the projector.
- **2** Set the input to the projector to INPUT B (VPL-PX15) or INPUT C (VPL-FX51). The Network Projector window appears.

Names and functions of the Network Projector window



My Projector icon

Browses the folders in the projector.

Double-clicking the icon shows the Memory card icon, etc.

2 Remote Desktop icon

Double-click the icon to use the Remote Desktop function.

③ Presentation Viewer icon

Select when you want to run a presentation using the file created with PowerPoint or you want to project an Excel or Word file on the projector.

Internet Browser icon

Double-clicking the icon connects to the Internet.

6 Image Viewer icon

Double-clicking the icon starts Image Viewer for running a slide show using image files stored in the projector or memory card.

6 Start menu

IP address

Shows the IP address of the projector. You can verify it when you are accessing the projector from a computer.

8 Screen keyboard icon

Clicking the icon displays the screen keyboard on the projector screen. You can operate the projector for setups or enter a URL by using the supplied Remote Commander. The screen keyboard has two pages. Clicking the Shift key changes the page.

■ About the supplied Remote Commander


- When the PJ/NETWORK select switch on the supplied Remote Commander is set to NETWORK, the TAB, ESCAPE, ENTER and arrow keys on the Commander function the same as those on the keyboard.
- Pressing the R CLICK key on the supplied Remote Commander on the screen keyboard icon opens the sub menu. Clicking Remote, then On enables you to use the arrow keys on the Remote Commander as those on the screen keyboard and to select the keys.

Olock

Desktop icon

Running a Presentation of a PowerPoint File Using the Slide Viewer

You can run a presentation by using a file with PowerPoint stored in a computer located in the same conference room or far from the projector. Even when a computer is not connected to the projector, you can also start the presentation using a file stored in the projector's storage or in the memory card installed into the PC CARD slot.



Menu bar

Menu	Command	Function
File	Open	Opens files stored in the projector.
	Recent Files	Opens the recently used files which are shown in the submenu.
	About	Indicates version information on the program.
	Close	Closes the currently displayed file.
View	Note View	Shows a slide in Note View mode.
	Slide View	Shows a slide in Slide View mode.
	Slide Show	Runs a slide show.
Slide Show	View Show	Runs a slide show.
	Set Up Show	Sets up the slide show.
	Select Slide	Selects to appear or disappear the slide.

(continued)

2 ★/★ (Move Slide up/down) buttons

Changes the order of the slide display.

(Note View) button Shows a slide and speaker's note.

(I image: Slide View) button Shows a slide.

(Slide Show) button

Runs a slide show.

6 Show list box

Click we to open the drop-down list and select the Custom Show you want to display.

7 🛯 (Help) button

Click to display the Help topic for the Slide Viewer.

8 File name

The name of a file is displayed.

Running a presentation

Using a file stored in a computer connected to the LAN

- **1** Double-click the My Projector icon in the Network Projector window.
- 2 Enter "\\ xxxx (name of a computer you want to access)" in the address column, then click the Enter button.

If the password is set for the selected computer, enter the password.

The shared folders for the computer are displayed.

Note

You have to set "On-board LAN" (page 10 (GB)) or "wireless LAN" (pages 11 (GB) - 12 (GB)) and also set share files with a computer you want to access.

3 Select the folder which contains the PowerPoint file (.ppt or .pps file) you want to run a presentation, then double-click that file. The Slide Viewer starts.

- When you want to set up the slide show, click Set Up Show from the View Show menu. The Set Up Show dialog box opens. For details, see Help for Slide Viewer.
- **5** Click Run from the View Show menu to run the slide show.

Using a file stored in the projector or in the memory card

- Double-click the Presentation Viewer icon in the Network Projector window.
 The Presentation Viewer starts, and the Open File dialog box appears.
- 2 From Storage (for storage) or Storage Card (for the memory card) of My Projector, select the PowerPoint file you want, and click the OK button. The Slide Viewer starts, and the selected file appears in slide view.
- **3** Perform steps **4** and **5** in "Using a file stored in a computer connected to the LAN."

Switching the slide view mode

Slide Viewer has three view modes; Slide Show, Slide View and Note View, each of which gives you a different way of showing a slide. Display a view by clicking its corresponding command from the View menu. Clicking its button on the tool bar also switches the view.


About Help for the Slide Viewer

For details on operations with the Slide Viewer, see Help. Clicking the № button on the tool bar opens the Help topic.

Projecting an Excel File Using the Worksheet Viewer or Word File Using the Document Viewer

You can project Excel or Word files stored in a computer on the same LAN. You can also project those stored in the projector or in the memory card without connecting a computer.

About the Worksheet Viewer window



Name box

Identifies the currently selected cell.

2 Menu bar

Menu	Command	Function
File	Open	Opens files stored in the projector.
	Recent Files	Opens the recently used files which are shown in the submenu.
	About	Indicates version information on the program.
	Close	Closes the currently displayed file.
View	Zoom	Opens the Zoom dialog box to enlarge or reduce the display.
	Split (Remove Split*)	Splits the displayed window into multiple panes.
	Row	Height: Sets height in Set Row Height dialog box. Auto Fit: Adjusts height automatically.
	Column	Width: Sets width in Set Column Width dialog box. Auto Fit: Adjusts width within the selected range.

* When Split is selected, the command in parentheses is displayed. Selecting it restores the normal window.

Sheet tabs

Displays the names of sheets. Click the sheet tab to make a sheet active.

Zoom box

Click \blacksquare to select the magnification to reduce or enlarge the display of an active worksheet.

6 Cell contents bar


Displays the result or constant value of the active cell.

6 № (Help) button

Displays the Help topic for the Worksheet Viewer.

(continued)

About the Document Viewer window



Menu bar

Menu	Command	Function
File	Open	Opens files stored in the projector.
	Recent files	Recently stored files are displayed. Clicking one of them opens that file.
	About	Indicates version information on the program.
	Close	Closes the currently displayed file.
View	Page Width	Enlarges or reduces the displayed page so that the width of the page fits the window.
	Whole Page	Reduces the displayed page so that the whole page fits the window.
	2 Pages	Displays two pages at the same time in the window.
	Zoom	Opens the Zoom dialog box for enlarging or reducing the displayed window.
	Full Screen	Displays the pop-up menu for changing the currently displayed method.

2 Zoom box

Click \bigvee to select the magnification to reduce or enlarge the displayed page.

🕄 🛯 (Help) button

Displays the Help topic for the Document Viewer.

Projecting an Excel or Word file

Using a file stored in a computer connected to the LAN

- Follow steps 1 and 2 in "Running a presentation
 Using a file stored in a computer connected to
 the LAN" on page 22 (GB).
- **2** Select the folder which contains an Excel or Word file you want to project on the projector, then double-click that file.

If the password is set for the selected computer, enter the password.

When you select the Excel file, Worksheet Viewer starts and a worksheet of the selected file is projected on the projector. When selecting the Word file, Document Viewer starts and the first page of the document is projected.

Using a file stored in the projector or in the memory card

- Double-click the Presentation Viewer icon in the Network Projector window.
 The Presentation Viewer starts, and the Open File dialog box appears.
- 2 From Storage (for storage) or Storage Card (for the memory card) of My Projector, select the Excel or Word file you want to project, and click the OK button.

When you select the Excel file, Worksheet Viewer starts and a worksheet of the selected file is projected on the projector. When selecting the Word file, Document Viewer starts and the first page of the document is projected.

Changing the size or display area of the projected worksheet

When you want to zoom in or out the projected worksheet or page, or change the area of the worksheet in view, see Help for Worksheet Viewer or Document Viewer.

About Help for Worksheet Viewer or Document Viewer


For details on operation with Worksheet Viewer or Document Viewer, see Help. Clicking the M button on the tool bar opens the Help topic.

Running a Slide Show Using the Image Viewer

You can display thumbnail images of the files stored in the projector or a memory card installed in the projector, then run a slide show by selecting the images you want.

When you start the Image Viewer of the projector and select the folder which contains the files you want, the main window opens.

About the main window of the Image Viewer



● Mathematical Help) button

Click to display the Help topic for the Image Viewer.

Ø Slide

Clicking a slide displays a green frame around the slide. This indicates that the slide is selected.

3 🛃 (Slide Show Setting) button

Opens the Slide Show Setting dialog box for zooming, rotating, etc.

🕘 🔚 (View Show) button

Clicking the button opens the sub menu for advancing a slide.

(Information) button

Opens the information dialog box of the selected slide.

🗿 🔍 (Full screen) button

Displays the full-screen window of a slide you choose.

Menu bar

Menu	Command	Function
File	About	Indicates version information on the program.
	Close	Closes the currently displayed file.
View	Full Screen	Displays the full-screen window of an image you choose.
	Information	Opens the information dialog box of the selected image.
	Sort slides	Sorts the slides in a folder by specified order.
Slide Show	View Show	Runs a slide show by advancing a slide selected in the sub menu.
	Slide Show Setting	Sets up the slide show in detail.
	Select all	Selects all the slides included in the thumbnail window.
	Clear all	Cancels any selection of slides in thumbnail images.
	Load	Loads the slide show setting file stored.
	Save	Stores the current slide show setting as a setting file (Extension is ".SHO.")

Folder dialog box

Browses the folders stored in the projector or a memory card installed in the projector.

Slide display area

Displays thumbnail images of the slides included in the folder you select.

(continued)

Displaying a full-screen image

You can display a full-screen image of an thumbnail image selected from the main window.

- **1** Double-click the Image Viewer icon in the Network Projector window. The Image Viewer starts.
- **2** Select the folder which contains the image files you want to display from the folder dialog box. You can choose the folder stored in the projector or a memory card installed in the projector. The main window opens, showing thumbnail images of the slides contained in the selected folder.
- Select a slide you want to display by clicking a thumbnail slide. The green frame appears on the selected slide.
- **4** Right-click the slide to select Full Screen, click Full Screen from the View menu, or click the 🔍 button on the tool bar.

The slide is displayed to fit the projector screen.


Running a slide show

- Follow steps 1 and 2 in "Displaying a full-screen image."
- **2** Select slides you want to use for your slide show.
 - Check the Slide Show check box on each slide you want to use. Check all the slides you are using.
 - To use all of the slides in the selected folder. click Select all from the Slide Show menu.
 - If you have already stored the slide show setting files, click Load... from the Slide Show menu to display the Load Slide show setting file dialog box. Select the file you want.

For details on the Slide show setting files, see "Saving the slide show setting."

3 When you want to set up the slide, such as zooming or rotating of an image, click Slide Show Setting from the Slide Show menu or click the button on the tool bar.

The Slide Show Setting dialog box appears.



Change the settings and click the OK or Save button.

Note

When projecting a large size image file such as those in UXGA format, it may not be opened or rotated due to lack of memory. In this case, reduce the image to obtain a smaller file size.

4 Click View Show from the Slide Show menu, or click the 🔚 button on the tool bar. The sub menu for choosing how to advance a slide opens. Clicking one of the options starts a slide show.

Saving the slide show setting

You can run a slide show repeatedly by using the files stored as the slide show setting files (.SHO files). You can also change the settings of the stored setting files.

To save the file

1 Click Save... from the Slide Show menu. The Save Slide show setting file dialog box opens.



2 Enter the file name, then click the OK button. The saved files are shown in the Load Slide show setting file dialog box.

To save after changing the settings

Click Slide Show Setting from the Slide Show menu to open the Slide Show Setting dialog box, and change the settings. Click the Save button to open the Save Slide show setting file dialog box. Follow step **2**.

To change the settings after saving

1 Click Slide Show Setting from the Slide Show menu.

The Slide Show Setting dialog box opens.

2 Click Load.

The Load Slide show setting file dialog box opens.



3 Select the file for which you want to change the settings, and click the OK button. The Slide Show Setting dialog box opens.

4 Change the settings, then click the Save button.

To change the setting in the main window

- 1 Click Load... from the Slide Show menu. The Load Slide show setting file dialog box opens.
- 2 Select the file you want to change, and click the OK button. The main window opens.
- **3** Change the checks in the Slide Show check boxes of the slides.

About Help for Image Viewer

For details on operations with Image Viewer, see Help. Clicking the № button on the tool bar opens the Help topic.

Connecting to the Internet

- **1** Double-click the Internet Browser icon in the Network Projector window. The Internet Browser window appears.
- **2** Click the software keyboard icon on the task bar to display the screen keyboard, then enter the address for the homepage you want.

Using the Remote Desktop Function

The projector is compatible with Remote Desktop feature for Windows XP Professional. The feature allows the projector to access all the data stored in a computer equipped with Windows XP Professional on the same LAN. Only a single projector in a conference room allows running a presentation.

Note

To use the Remote Desktop function, it it required for the computer to register the remote desktop users who are permitted to get access to the computer. Set the Remote Desktop setting by clicking Control Panel, selecting System and then System Properties.

- Double-click the Remote Desktop icon on the desktop window of the projector. The Remote Desktop setting window opens.
- 2 Enter the IP address of the computer in which the file you want is stored.The log on window for the computer is displayed.
- **3** Enter the user name and password of the computer. When the projector logs on to the computer, the desktop window of the computer appears on the projector screen.
- **4** Operate the projector to select the file you want and to run a presentation.

Preparations

Before starting

■ For VPL-PX15

Confirm that the INPUT-B FUNC. is set to ON in the INSTALL SETTING menu.

■ For VPL-FX51

Confirm that the INPUT-C FUNC. is set to ON in the INSTALL SETTING menu.

Starting the browser for accessing the projector

In order to control the projector from a computer, you have to access the projector by starting the browser on the computer. Suitable browsers are Internet Explorer 5.0 or later versions.

If your computer is equipped with Windows Me or Windows XP and you use the Auto Projector Search function, the following procedure is not necessary. Access the projector by using the procedure described in "Accessing the projector using the Auto Projector Search function."

- **1** Turn on the projector.
- **2** Set the input to the projector to INPUT B (VPL-PX15) or INPUT C (VPL-FX51).
- **3** Switch on the computer.
- **4** Start the browser on the computer.
- **5** Enter the IP address of the projector.

Type "http://xxx.xxx.xxx (for the IP address of the projector)."

You can verify the IP address as it is displayed on the task bar in the Network Projector window. The Application Select window appears.

When the password is set for the projector, the password setting dialog box appears. Enter the Name and Password for User.

For information on the Application Select window, see "Names and functions of the Application Select window."

Operations that follow the above steps are shown on pages 29 (GB) to 38 (GB).

Notes

- Do not have access to the projector from two or more computers simultaneously.
- If the browser of your computer is set to "Access the Internet using a proxy server," enter the IP address of the projector in the box "Access the Internet without using a proxy server" when you have access to the projector from your computer.
- The computer may not accept the password for the projector, depending on the version of the browser. In this case, restart the browser.
- If the browser on a computer exits without closing the application, the projector automatically returns to the initial Network Projector window after about 30 seconds. In this case, restart the browser.

Accessing the projector using the Auto Projector Search function

When you are using a computer equipped with Windows Me or Windows XP, you can access the projector without starting the browser on the computer.

Note

It is necessary to add the Universal Plug and Play component on the computer to use the Auto Projector Search function. Click Control Panel, then select Add/ Remove Programs.

From the Start menu, click Programs, System, and then Service Manager to display the control window. In the control window, press ► to use once or set the start-up mode of the property to Auto to use thereafter.

- **1** Double-click the My Network icon.
- **2** Double-click the projector icon. The Application Select window appears.


When the password is set for the projector, the password setting dialog box appears. Enter the Name and Password for User.

For information on the Application Select window, see "Names and functions of the Application Select window."

Operations that follow the above steps are shown on pages 29 (GB) to 38 (GB).

Names and functions of the Application Select window

Having access to the projector opens the Application Select window. The following shows the names and functions of the icons and buttons in the window.



Language select button

Clicking 💌 opens the language select drop-down list. Each window has help sentences shown on the lower part of the window. You can display them in English, French, German, Spanish or Italian.

Ø FILE MANAGER icon

Starts the File Manager to manage the files stored in the projector.

③ IMAGE VIEWER icon

Opens the setup window for projecting image files.

PRESENTATION VIEWER icon

Opens the select window for starting the PowerPoint viewer (Slide Viewer), Excel viewer (Worksheet Viewer) or Word viewer (Document Viewer).

⑤ I/⁽) (on/standby) button

Turns the projector on or sets it to standby mode.

6 Help

Resting the pointer over each item displays the instructions for the item. This makes your operations easier in each window.

Input select buttons

Select the input to the projector. The INPUT C button does not exist in the window for the VPL-PX15.

Ø MORE... button

Opens the control window for the projector.

Notes

- It may take time to display the file depending on your network configuration.
- Capacity of one file to be sent is 15 MB maximum.
- As the Slide Viewer, Worksheet Viewer and Document Viewer are the basic PowerPoint, Excel and Word functions, respectively, they do not support some features of other software. We recommend you should project the file you are using for your presentation on the projector before starting the presentation.
- The display on the computer may be different from the original display from the projector.
- The following fonts are available for the Presentation Viewer; Arial, Arial Black, Comic Sans MS, Courier New, Georgia, Impact, Symbol, Tahoma, Times New Roman, Verdana and Wingdings.

Running a Presentation of a PowerPoint File Using the Slide Viewer

When you intend to run a presentation with PowerPoint in a conference room, you can control the presentation by operating your computer in the same room or in the location far away from the projector.

What you can do with the Slide Viewer

You can

- run a slide show using the file created with PowerPoint.
- show a custom slide show if created.
- show a speaker's note or hide it.
- show a slide or hide it.
- set timings to advance a slide during a slide show. You can select an automatic or manual slide show.

Running a presentation


- 1 Click the PRESENTATION VIEWER icon in the Application Select window. The Look In window appears.
- **2** Click to select where to search for the file you want to use for your presentation.
 - **COMPUTER:** To select a file stored in a computer
 - **PROJECTOR:** To select a file stored in the projector

The File Select window appears.

3 Select the file you want to use for your presentation.

When you select COMPUTER in step 2

Clicking Browse opens the file select window on a computer. Click the PowerPoint file (.ppt or .pps file) you want. You can also select the file by entering the file name in the Browse text box. The selected file name is displayed in the Browse text box.



To store the selected file into the projector

Click to check the "save in projector" checkbox. You can set the password for the file, if necessary. Specify the password in the "password" text box. This disables the file to open from now on unless you enter the password.

The file will be stored when you click the Set Up or View button.

Note


When you delete a file using File Manager, entering the password is not required even if the password is set for the file.

When you select PROJECTOR in step 2

The file list showing the files stored in the projector or a memory card appears. Click the PowerPoint file you want. The selected file name is displayed in the text box.

Sony Network Projector
Presentation File Select
View Set Up
Store Store None B plan_A SODK PowerPoint 08/16/99 04:13 B presentation 221kB PowerPoint 08/16/99 04:13
Finds a file you want to run in the presentation in the file list.
BACK A HOME
O I NUSO GAUDO INVITA INVITE INVITE MOL

4 Set up your slide show, if necessary. Click the Set Up button in the File Select window.
The Set Up Show window appears. You can specify slides you want to use for your slide show and set how to advance a slide in the slide show.
Resting the mouse pointer over each item shows its instruction on the lower part of the window.



Note

If you are running a presentation using the file stored in a computer, the file is transferred to the projector at the time you click the Set Up button. It will take a little time to display the Set Up Show window on the computer. How long it takes depends on the file size. During this time a message will appear.

5 Click the View button in the File Select window or click the View Show button in the Set Up Show window.

The slide show starts.

Note

If you are running a presentation using the file stored in a computer, the file is transferred to the projector at the time you click the View button. It will take a little time to display a slide show on the projector screen. How long it takes depends on the file size. During this time a message will appear.

To end the slide show

Click the End Show button. (See page 32 (GB).) The File Select window returns.

Note


If the message "Projector's memory is full" appears when clicking the View or Set Up button, delete unnecessary files stored in the projector using the File Manager (page 37 (GB)), then try to run the slide show again. If the message "File size is too large." appears, reduce the file size, then try to run the slide show again.

Tip:

You may make it smaller by clicking Option, then Save from the Tools menu, and unchecking Save Fast in the PowerPoint application.

About the window displayed while the presentation is running

The following window is displayed during a presentation.



ONOTES button

Selects to display/remove a speaker's note.

2 SLIDE button

Selects to display/remove a slide show on/from a computer's display.

• File name/slide number

Shows the name of a file and which slide is displayed.

(continued)

4 Slide

Shows the currently displayed slide in the slide show. The projector's screen displays only this slide.

⑤ ◄ PREVIOUS button

Returns to the previous slide or Animation setting during the slide show.

6 Slide text box

Clicking vote opens the slide name drop-down list. When you select a specific slide from the list, it will be shown.

⑦ NEXT ► button

Advances to the next slide or Animation setting immediately.

Set Up Show button

Returns to the Set Up Show window.

End Show button

Ends or suspends the slide show to return to the File Select window.

Note

Displays a speaker's note. It is not displayed on the projector screen.

① ▲ HOME button

Returns to the Application Select window.

Projecting an Excel File Using the Worksheet Viewer or Word File Using the Document Viewer

You can project an Excel or Word file on the projector by operating a computer.

When you select an Excel file, the Worksheet Viewer starts and a worksheet of the selected file is projected on the projector screen. When you select an Excel file, the Document Viewer starts and the first page of the selected file is projected on the projector screen.

What you can do with the Worksheet Viewer or Document Viewer

You can

- display Excel worksheets or Word documents to fill the projector screen.
- zoom in or out the projected worksheet or document page.

Note

As the Worksheet Viewer or Document Viewer are a simple Excel or Word viewer function, it does not support some features.

Projecting an Excel or Word file

1 Follow steps 1 to 3 in "Running a Presentation Using the Slide Viewer — Running a presentation" on page 30 (GB). Make sure to select an Excel file (.xls file) or Word file (.doc file) in step 3.

2 Click the View button.

The Worksheet Viewer starts when you select an Excel file, and the worksheet of the selcted file is displayed on the projector.

The Document Viewer starts when you select a Word file, and the first page of the selected file is displayed on the projector.

Example: Worksheet Viewer window


S	Sor	ny Networ	k Projec	tor				
	Wo	orksheet Viev	<i>i</i> er					
	File	Name :						
	Sale	esReport.xls						Sheet: Sheet1 💌
1.	1	A	в	С	D	E	_	Pane: Top Left 💌
1	2	Sales Repo	rt					Zoom: 75% 💌
1	3	Gales Repo						
	4		10	20	30	40		
	5	Region A	1000	1000	1500	2000		
	6	Region B	1500	2000	2000	2500		
	7	Region C	2000	2000	3000	4000		
	8	Region D	500	500	1000	1500		
	9	Region E	1000	1500	1500	2000		
	10	Region F	1500	1500	2000	2500		
	11	Region G	1000	1000	1500	1500		
	12	Region H	1000	1500	2000	2500		
	13						⊢	
		cted cell: A1	. =			-		END A HOME
P								
н.								
h	_	_	_	-			-	
	6		5 7		P.J CON		-	
	-	ப்		VIDE0 -	SELECT	INPUT A	INPUT	B INPUT C MORE
_								

When you rest the mouse pointer over each button or item, its instructions will appear on the bottom of the window.

Notes

- The range of the displayed area of a worksheet on a computer and that of the projected area on the projector is not the same.
- When you click a cell on a computer for worksheet Viewer, the cell becomes active if the selected cell is within the area displayed on the projector. If the selected cell is outside the displayed area, the area with the selected cell is centered on the projector's display.

About the window displayed while the Worksheet Viewer is running



❶ ≚ button

Selects the bottom rightmost cell of the displayed worksheet.

2 Zoom text box

Clicking vopens the drop-down list to select the ratio of enlargement or reduction. The worksheet is enlarged or reduced with the currently selected cell centered.

Or Pane text box

When the displayed worksheet is split into multiple panes, click 💌 to open the drop-down list and select the desired pane from Top Left, Top Right, Bottom Left and Bottom Right.

Output Sheet text box

Clicking opens the drop-down list of the sheet names included in the displayed workbook. Selecting a sheet name displays the selected sheet.

🗿 📧 button

Selects the top leftmost cell of the worksheet.

6 File Name

Shows the file name currently displayed.

Selected Cell

Shows the column and row numbers of the selected cell.

8 Worksheet

Displays the worksheet which is currently projected on the projector.

Scroll bars

Use to scroll the area displayed on the computer left or right, or up or down. To scroll, drag the box or click the arrows.

END button

Ends or suspends the worksheet display to return to the File Select window.

① ▲ Home button

Returns to the Application Select window.


Oscill buttons

Each click \blacktriangleleft or \blacktriangleright button moves the area displayed on the projector one row to the left or right.

Each click \blacklozenge or \blacklozenge button moves the area displayed on the projector one line up or down.

(continued)

About the window displayed while the Document Viewer is running



1 Scroll buttons

Clicking \triangleleft or \rightarrow button scrolls the displayed page left or right.

Clicking \blacklozenge or \blacklozenge button scrolls the displayed page up or down.

2 toutton

Displays the previous page.

3 Zoom text box

Clicking rough opens the drop-down list to select the ratio of enlargement or reduction. The displayed page is enlarged or reduced.

Page text box

Clicking round opens the drop-down list of the page numbers. Selecting the page number displays the selected page.

5 File name

Shows the name of the currently displayed Word file.

O UPDATE button

Clicking this buttom displays the same window as that being projected on the projector.

O Document page

Displays the page which is currently projected on the projector by clicking the UPDATE button.

B END button

Ends or suspends the Word file display to return to the File Select window.

③ ▲ HOME button

Returns to the Application Select window.

Displays the next page.

Projecting an Image Using the Image Viewer

You can project an image file stored in any computer on the same LAN or stored in the projector's storage or in the memory card installed in the projector. You can also run a slide show using the slide show setting file (.SHO file) preset in the projector.

Projecting an image stored in a computer on the projector

1 Click the IMAGE VIEWER icon in the Application Select window. The Look In window appears.

2 Click COMPUTER.

The Image Viewer of the projector starts, and the Image Viewer window opens.

Sony Network Projector	t i i i i i i i i i i i i i i i i i i i			
lmage Viewer				
File Name : Mountain.jpg	E:¥River.jpg	Browse	(SHOW
	Temporary File :	Size	Туре	Modified
	Flower.png	205KB	PNG file	8/16/1999
	Tree.gif	21KB	GIF file	8/16/1999
	River.jpg	57KB	JPG file	8/16/1999
Zoom : 100 💌	Mountain. jpg	26KB	JPG file	8/16/1999
Rotate :	<u>Building bmp</u>	1260KB	BMP file	8/16/1999
•		8	END	(HOME
	PJ CONTROL			
	0 S-VIDEO (INPUT /	INPUT B	INPUT C	MORE

Resting the mouse pointer over each item shows its instruction on the lower part of the window.

3 Select an image file to display.

Click Browse to open the file select window on a computer. Double-click the file you want. The selected file name is displayed in the Browse text box.

4 Click the SHOW button. A full-screen image of the selected file is displayed on the projector.

Note

When projecting a large size image file such as those in UXGA format, it cannot be opened due to lack of memory. In this case, reduce the image to obtain a smaller file size.

To save time taken for transferring data

When clicking the SHOW button, the file is transferred to the projector. It will take a little time to display an image on the projector's screen. To display the image immediately, transfer all the files you want to use to the projector before starting your presentation.

1 After step **3** in "Projecting an image stored in a computer on the projector," click the SEND button.

The selected file name appears in the Temporary File list and the file is transferred to the projector. Repeat this step until all the files you want are shown in the Temporary File dialog box.


2 Double-click the file name listed in the Temporary File dialog box.

A full-screen image of the selected file is displayed on the projector.

Note

If the memory of the Temporary File list is full, the data transferred earlier will be erased.

About the window displayed while the Image Viewer is running



File name

Shows the file name of the currently displayed image.

Ø Slide

By clicking the SHOW button or the file name listed in the Temporary File, the current picture projected on the projector appears.

O Zoom text box

Clicking ropens the drop-down list to select the ratio of enlargement or reduction for the image.

Output text box

Clicking ropens the drop-down list to select the angle of rotation for the image.

Note

When projecting a large size image file such as those in UXGA format, it cannot be rotated due to lack of momory. In this case, reduce the image to obtain a smaller file size.

5 Scroll buttons

Clicking the arrows changes the display area of the image on the screen, if the enlarged image does not fit the screen.

6 END button

Ends or suspends the full-screen display to return to the File Select window.

Returns to the Application Select window.

(continued) 35 (GB)

Note

When you exit the Image Viewer window by clicking the END or HOME button, the files listed in the Temporary File will be automatically erased. To store the files, add them to the projector using the File Manager function.

For details, see "Using File Manager" on page 37 (GB).

Running a presentation using an image file stored in the projector

1 Click the IMAGE VIEWER icon in the Application Select window. The Look In window appears.

2 Click PROJECTOR.

The Image Viewer of the projector starts, and the Folder/.SHO File Select window opens.

Sony Network P	rojector			
Image View	Folder/.SHO File S	elect		
507	\Storage\Documents\test.sh \Storage\Documents		<u>s</u>	ELECT
	Folder	Name <u>test.sho</u> <u>Travel.sho</u>	Size Type 1KB SHO fi 1KB SHO fi	
	Selects a folder stored in the (projector or the sl	ide show settin	g file preset
	on the projector (.SHO file).			
	DME			
	PJ CON VIDEO S-VIDEO	TROL	(INPUT C	MORE

3 Click the folder you want or the folder that contains the slide show setting file (.SHO file) in the Folder list on the left of the window. The contents of the selected folder are listed on the right.

For details on .SHO files, see "Saving the slide show setting" on page 26 (GB).

4 Select a folder or .SHO file you want to use, then click the SELECT button.

The Image Viewer window appears (see the right column).

5 Select an image file you want to project on the projector.

When you select a folder in step 4

Image files contained in the selected folder are listed on the right.

File Name : Mountain.jpg	\Storage\Documents			
Zoom : 100 V Rotate :	Name Building bmp Flower, png River, jng Mountain, jng Tree.gif	500 1260KB 205KB 57KB 26KB 21KB	JPG file	Modified 8/16/1995 8/16/1996 8/16/1996 8/16/1995 8/16/1995
			END	

END button Ends or suspends the display to return to the File Select window.

▲ HOME button Returns to the Application Select window.

Click the file you want.

A full-screen image of the selected file is projected on the projector.

Resting the mouse pointer over each item on the left of the window shows its instructions on the lower part.

When you select an .SHO file in step 4 The selected .SHO file appears on the right.

Sony Network Projector	1			
lmage Viewer				
File Name : Mountain.jpg	 Manually Automatically Automatically (cont Travel.sho 	inuously)	(SHOW
	Name Flower.png Mountain.jpg River.jpg	Size 2 290x445 580x393 386x580	200m 100 100 100	Orientation O° O°
PREVIOUS NEXT >			END	HOME
	PJ CONTROL	INPUT B	NPUT C	MORE

Select how to advance slides, and click the SHOW button. The slide show starts.

Resting the mouse pointer over each item on the window shows its instructions on the lower part.

About the window displayed while the Image Viewer is running

The same window as that in "About the window displayed while the Image Viewer is running" on page 35 (GB) appears.

The NEXT button on the .SHO file select window is to advance to the next slide immediately during the slide show. The PREVIOUS button is to go back to the previous slide.

Using File Manager

You can manage the files stored in the projector from a computer by a simple operation. The File Manager function enables you to delete unnecessary files stored in the projector or to add files stored in a computer to the projector's storage.


Use File Manager while checking the currently used memory and largest unused memory of the projector displayed in the File Manager window.

Adding files to the projector using File Manager

- Click the FILE MANAGER icon in the Application Select window. The File Manager window appears.
- **2** Search for the file stored in a computer you want to add to the projector.

Click the Browse... button in the Add File section to open the file select window on the computer. Select the file you want. You can also select the file by entering the file name in the Browse... text box.

You can set the password for the selected file in this step. Specify the password in the "password" text box. Setting the password disables you to open the file from now on unless you enter the password. Used memory/memory capacity



3 Click the Add button. The selected file is stored in the projector.

Deleting files from the projector using File Manager

1 Click the FILE MANAGER icon in the Application Select window.

The File Manager window appears and the list of files stored in the projector pops up.

- 2 Select the file you want to delete. You can check all the files you want to delete.
- **3** Click the Delete button. All the files you have checked are removed from the file list.

Note

You can delete a file even if the password is set for the file.

Controlling the Projector from a Computer

You can perform various adjustments and settings of the projector on a computer's display. Three control windows are available; GENERAL, PICTURE CTRL and SETTINGS windows, each with different functions.


The functions of the buttons in the windows are the same as those on the Remote Commander supplied with the projector.

For details on the buttons, see the Operating Instructions of the projector.

The illustrations shown in the steps below are for the VPL-PX15.


- 1 Click the MORE... button in the PJ CONTROL section. The GENERAL window appears.
- **2** Click the function tab to select the window you want.

GENERAL window



(VPL-PX15)

PICTURE CTRL window



(VPL-PX15)


■ For VPL-PX15

The COLOR TEMP (HIGH, LOW) buttons function the same as the settings in the menu.

For VPL-FX51

The DDE (OFF, PROGRESSIVE, FILM) and RGB ENHANCER +/- buttons function the same as the settings in the menus.

SETTINGS window



(VPL-PX15)

■ For VPL-PX15

The ASPECT (4:3, 16:9) and STATUS (ON, OFF) buttons function the same as the settings in the menu.

For VPL-FX51

The ASPECT (4:3, 16:9) and LAMP MODE (STANDARD, LOW) buttons function the same as the settings in the menus.


3 Click the button to adjust or set.

Checking the Indicators on the Projector — when operating from a computer

You can check the present status of the indicators on the control panel of the projector on a computer display.

- **1** Start Internet Explorer 5.0 or later versions on the computer.
- Type "http://xxx.xxx.xxx (for the IP address of the projector)/info" as a URL.
 If you do not change the factory-set IP address, type "http://192.168.0.1/info" (when using an onboard LAN).
- **3** Enter the name and password of the Administrator. The Information window appears.

The illustration below is for the VPL-PX15.



Projector Status

Shows the present status of the projector.

Projector

Shows the information on the projector.

System

Shows the versions of the OS (Operating System) and application currently used.

4 UPDATE button

Click to update the latest information.

G Error Status

Shows the present status of the indicators on the control panel of the projector.

For information on the indicators, see the Operating Instructions.

Using the e-Mail Report Function

What you can do with the e-Mail Report function

- Reports installation status of the projector, user information, etc. periodically. You can specify the transmitting date of mails (Regular Report).
- If any error occurs with the projector, reports it immediately (Error Report).
- Sends a warning mail when a preset used time of the projector lamp has been reached (Lamp Reminder).
- Sends a warning mail when a preset maintenance time of the projector has been reached (Maintenance Reminder).

Setting for e-Mail Report function — when operating from the projector

To use the e-Mail Report function, set the mail addresses and date to where and when mail is to be sent, and which mail functions you are using.

- From the Start menu, select Control Panel, then select e-Mail Report.The e-Mail setting window opens.
- **2** Click the Mail tab. The following window opens.

ail Server Address T0: CC:	
Report Timing Regular Report At 8:00 Every Week on Days Mon Tue Wed Thu Fri Sat Sun Every Month on Day 1	Error Report Lamp Reminder 1000 hours Maintenance Reminder Elapsed Hours RESET

- **3** Set the addresses where mail is to be sent. Enter mail addresses in the TO: and CC: text boxes. The same mail can be sent to three different addresses at the same time.
- **4** Set the time and day when mail is to be sent, and the mail function you are using (Error Report, Lamp Reminder and/or Maintenance Reminder).
- **5** Click the Server tab.

The mail server setting window opens.

ail Server	
Server	
Mail Address :	
SMTP:	Port : 25
Mail Form	
 Standard 	◯ Simple
	Test Mail

6 Set the allocated mail address, and SMTP of the mail server.

For details, refer to the e-Mail Report Help.

7 When all the settings are complete, click the OK button.

To send test mail

You can send mail as a test to confirm whether it is sent to the specified addresses. Click the Test Mail button.

About Help for e-Mail Report

For details on operation with e-Mail Report function, see Help. Clicking the 2 button on the tool bar opens the Help topic.

Setting for e-Mail Report function — when operating from a computer

To use the e-Mail Report function, set the mail addresses and date to where and when mail is to be sent, and which mail functions you are using.



Display the Setup window on the computer. For how to display the Setup window, see "Opening the setup window" on page 14 (GB).

2 Click the e-Mail Report icon in the Setup window. The setting window of the e-Mail Report function opens.

See the explanations described below for how to set each item.

Address text boxes

Enter mail addresses in the TO: and CC: text boxes where you want to receive mail. The projector enables to send mail to three different addresses. You can enter up to 128 characters for each address.

Regular Report

A report on the present status of the projector, user information, etc. of the projector is periodically sent by mail.

Set the timing to send mail as follows:

- At: Specifies the time when mail is to be sent. Select the hour from the drop-down list.
- **Every Week on Days:** Selecting this check box allows mail to be sent on the selected days every week.
- Mon/Tue/Wed/Thu/Fri/Sat/Sun: Specifies the days of the week. You can check two or more days.
- **Every Month on Day:** Selecting this check box and selecting the day from the drop down list enables to send a mail on the defined day every month.

The Regular Report contains the following items:

- **Product Information:** Model name, Serial number, Version information
- **User Information:** User name, Organization name, Place where the projector is installed
- **Information:** Used time of the projector lamp, Lamp mode, etc.

Memo

APPLY button

Click when setting of all the items is complete.

4 Maintenance Reminder

Selecting this check box and entering the hours of use when maintenance is required for the projector in the text box enables you to receive mail that informs you when the preset time has been reached. You can specify the time between 1 and 99999 hours. The elapsed time is displayed in the Elapsed Hours text box. Selecting the RESET check box and clicking APPLY reset the elapsed time to zero.

6 NEXT button

Closes this window and opens the setting window for the mail server.

6 Lamp Reminder

Selecting this check box and entering the used hours of the projector lamp in the text box enables you to receive mail that informs you of the replacement time of the projector lamp when the preset time has been reached. You can specify the time between 1 and 9999 hours.

O Error Report

Selecting this check box allows sending of an error report if any error occurs with the projector.

Notes


- If the days of the week are specified without selecting the Every Week on Days check box, you cannot receive the Regular Report. If the preset day on the Every Month on Day does not exist in the month, you will receive mail on the last day of the month.
- You cannot specify the day of the week or day of the month if the Every Week on Days or Every Month on Day check box is not selected.
- Specifying the hours for Lamp Reminder or Maintenance Reminder is not available if the corresponding check box is not selected.



Setting the mail server — when operating from a computer

After the mail setting is complete, click the NEXT button.

The mail server setting window opens.



Mail Address

Type the allocated mail address. You can enter up to 128 characters.

Ø SMTP

Type the address of the mail server. You can enter up to 128 characters.

Mail Form

Selects the mail form from Standard or Simple. When Simple is selected, the mail with a simple message is sent in the following cases:

- an error occurs.
- a preset used time of the projector lamp has been reached.

4 BACK button

Closes this window and opens the mail setting window.

Test Mail

Sends mail as a test to confirm whether it is sent to the specified addresses. Select the Send check box, then click the APPLY button.

6 APPLY button

Click this button when the mail server setting is complete or when you send a test mail.

Note

If the following items have not been set or are incorrectly set, the error message appears and the test mail is disabled:

- TO: text box in the mail setting window
- Mail Address in the mail server window
- SMTP

Troubleshooting

If the projector appears to be operating erratically, try to diagnose and correct the problem, using the following guide. If the problem still persists, consult with qualified Sony personnel.

Setting/Connecting

Symptom	Causes and remedies
A connection to the network is not established.	 The PC card is not properly inserted into the PC CARD slot.
	 The cable is not properly connected to the ETHER connector.
	 The wireless LAN PC card and wireless LAN access point you are using are not the specified/recommended ones.
	→ Use the specified/recommended devices. Use of those not specified/ recommended may cause incorrect operation.
	For information on the specified/recommended cards, etc., see the attached "Specified/recommended PC Card."
	The network environment is not properly set up.
	→ Check the network configuration settings of the projector. (pages 10 (GB) - 12 (GB))
	→ When you control the projector by using the computer's Web browser, check the network settings on the computer as well.
	 When you use a wireless LAN PC card (VAIO/ORiNOCO), Enable is selected. → Select Disable. (page 10 (GB)).
	• When you are using the wireless LAN PC card, the wireless LAN is not properly set up.
	→ Check that the Access Point ID and Encryption Key in the Connecting Status dialog box are set to the same numbers as those of the connected access point (page 11 (GB)).
	When you are using the wireless LAN PC card, Peer to Peer mode is not properly set up.
	→ Select Peer to Peer only on a piece of equipment connected to the same wireless LAN (page 12 (GB)).
	 The channel of the access point is set to 12–14. → Set the channel of the access point to 1–11.
	• The wireless LAN PC card, memory card or access point still does not operate properly after checking the above.
	→ Consult with the manufacturer of the card or access point you use. When you are using the specified Sony wireless LAN PC card, consult with the qualified Sony personnel.
The computer cannot access to the projector.	 The setting of INPUT-B FUNC. (VPL-PX15) or INPUT-C FUNC. (VPL-FX51) in the INSTALL SETTING menu is not correct. → Set it to ON.
	• The browser of your computer is set to "Access the Internet using a proxy server."
	→ Enter the IP address of the projector in the box "Access the Internet without using a proxy server."
	You entered the projector's IP address started with 0 (zero).
	→ Do not enter 0 at the beggining of the number. Example: 192.168.000.001 →192.168.0.1

Presentation

Symptom	Causes and remedies
Fonts or styles change in a PowerPoint, Excel or Word file.	 In the text of the file, fonts or styles not supported by the Slide Viewer, Worksheet Viewer or Document Viewer are used. → Only the following fonts are available for the Slide Viewer. Other fonts will be replaced with these fonts; Arial, Arial Black, Comic Sans MS, Courier New, Georgia, Impact, Symbol, Tahoma, Times New Roman, Verdana, Wingdings. If replaced, an end of paragraph may change according to tab or pharagraph settings. Styles not supported by the Slide Viewer will be replaced with supported styles.

(continued) 43 (GB)

Presentation

Symptom	Causes and remedies
Some characters are not displayed in a PowerPoint, Excel or Word file.	You cannot display characters that the Slide Viewer, Worksheet Viewer or Document Viewer does not support. → Use the file created in English, French, Spanish, German, Italian, Chinese, Portuguese or Korean which are supported.
Some features of a PowerPoint, Excel or Word file are not properly displayed or such effects are not displayed at all.	 The file is using the features that are not supported by the Slide Viewer, Worksheet Viewer or Document Viewer of the projector, or the file is created with PowerPoint 2002, Excel 2002 or Word 2002. → The features will be replaced with those that are supported. Apply effects that are supported if nothing is displayed.
A slide show cannot be run. The message "Projector's storage is full. Delete the file stored in the projector." appears.	 The memory of the projector is full. → Delete unnecessary files stored in the projector using File Manager to increase memory capacity.
A slide show cannot be run. The message "File size is too large. Decrease file size in any way; for example, by dividing it into smaller files, then try to restart the slide show." appears.	 File size exceeds the capacity for transition to the projector. → Check empty memory capacity in the File Manager window, then decrease the file's capacity by dividing it into smaller files. → Click Option then Save from the Tool menu on the PowerPoint, then remove the check from Save Fast.

Internet browser

Symptom	Causes and remedies
Internet Browser for the projector cannot be started.	The projector is not connected to the LAN. → Check the setups for the On-board LAN and wireless LAN environment. (pages 10 (GB)–12 (GB))
You cannot get access to the home pages with the Internet browser of the projector, or some of them are not displayed.	 Plug-in software such as Media Player and Real Player is required, or a home page you are accessing is created in Java format. → As the Internet browser of the projector is not compatible with plug-in software, it cannot display home pages that use Media Player or Real Player. The browser of the projector is not compatible with Java format.

Others

Symptom	Causes and remedies
The Auto Projector Search or Remote Desktop function does not work.	 The necessary setting is not done on the connected computer. → Perform the necessary setting for the corresponding function on the computer (page 27 (GB) or page 28 (GB)).
The projector screen freezes.	The software of the projector is frozen. → Once you set INPUT-B FUNC. (VPL-PX15) or INPUT-C FUNC. (VPL-FX51) in the INSTALL SETTING menu to OFF, then reset it to ON.
The message "Password is set for the file. Enter password." appears.	 The password is set for the projector or the file. → Enter the password. When the IP address is not changed from the factory-preset one, enter "root" in the Name text box for Administrator.
The message "You might have entered the wrong password. Enter it again." appears.	The password you entered is not correct. → Enter the correct password.

© 2002 WESTTEK LLC. All Rights Reserved. WESTTEK and the WT Logo are registered trademarks of WESTTEK, LLC.

The SONY VPL-Series projector contains materials owned by Sony and Sony suppliers, including WESTTEK, LLC. Your purchase of the SONY VPL-Series projector gives you a limited right to use these materials, solely as a part of the SONY VPL-Series projector and only as necessary to use the SONY VPL-Series projector in the manner described in the accompanying documentation. Your purchase of the SONY VPL-Series projector does not transfer any ownership in these materials to you and you are forbidden to use them for any purpose other than as part of the SONY VPL-Series projector. These materials are protected by copyright law and international treaties. Any unauthorized use, reproduction or distribution of such materials, or any portion of them, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent permissible under law.